

REVISED DRAFT

WORK PLAN POST REMOVAL SAMPLING

**Bonneville Dam Project
Cascade Locks, Oregon**

January 2003

Prepared for:



U.S. Army Corps of Engineers, Portland District
333 SW First Avenue
Portland, Oregon 97208-2946

Prepared by:



111 S.W. Columbia, Suite 900
Portland, Oregon 97201-5814
25692710

TABLE OF CONTENTS

List of Abbreviations	iii
Section 1 Introduction.....	1-1
1.1 Investigation Objectives.....	1-1
1.2 Format and Purpose.....	1-2
Section 2 Site Description.....	2-1
2.1 Site Location and Features	2-1
2.2 Site and Regulatory Background.....	2-2
2.2.1 Site Background	2-2
2.2.2 Regulatory Background.....	2-3
Section 3 Summary of Previous Investigations	3-1
3.1 Upland Investigations by Contractors.....	3-1
3.2 Dredge Evaluations & Other Studies by USACE.....	3-1
3.3 Pile #1-Partial Removal – December 2000.....	3-3
3.4 In-Water Investigation – May 2001	3-3
3.5 First Powerhouse Trashboom Sediment Evaluation – January 2002.....	3-4
3.6 Off-Shore Debris Removal– March 2002	3-5
3.7 Bonneville Forebay Characterization – August 2002	3-5
Section 4 Conceptual Site Model	4-1
4.1 Known and Potential Sources of Contamination.....	4-1
4.2 Contaminants of Interest	4-2
4.3 Hydrology.....	4-4
4.4 Contaminant Transport From Upland Sources.....	4-5
4.5 Sediment Transport.....	4-6
4.5.1 Hydraulic Modeling.....	4-6
4.5.2 Sediment Characteristics.....	4-7
4.5.3 Sediment Transport.....	4-8
4.6 Preliminary Receptors.....	4-9
4.6.1 Human Health.....	4-9
4.6.2 Ecological.....	4-10
4.7 Conceptual Site Model Uncertainties.....	4-10
Section 5 Overview of Investigation Process & Data Needs Analysis.....	5-1
5.1 Nature and Extent	5-2
5.1.1 Source Area Groups.....	5-2
5.1.2 Potential Depositional Groups	5-3
5.2 Upstream Contribution.....	5-6
5.3 Risk Assessment.....	5-6
Section 6 Data Management and Quality Assurance Review.....	6-1
6.1 Data Management and Evaluation.....	6-1
6.2 Data Files and Records.....	6-1
6.3 Laboratory Quality Assurance	6-1

TABLE OF CONTENTS

6.4	Independent Technical Review	6-2
Section 7	Project Organization and Responsibilities.....	7-1
7.1	Site Access and Security.....	7-1
7.2	USACE Project Manager – Mark Dasso.....	7-1
7.3	USACE Technical Manager – Paul Huebschman.....	7-1
7.4	USACE Site Contact – Brian McCavitt	7-1
7.5	USACE Dive Safety Officer – Don Hibbs.....	7-2
7.6	DEQ Project Manager – Matt McClincy.....	7-2
7.7	URS Project Manager – Jeff Wallace	7-2
7.8	URS Analytical Chemistry Task Manager – Madi Novak.....	7-2
7.9	URS Field Investigation Task Manager – Chris Moody.....	7-2
7.10	URS Independent Technical Reviewer – David Weymann.....	7-3
7.11	Subcontractor Services.....	7-3
Section 8	Schedule.....	8-1
Section 9	References.....	9-1

TABLES

Table 4-1	Sediment Results-Metals
Table 4-2	Sediment Detections
Table 5-1	Sampling Rationale by Sample Group
Table 5-2	Sampling Method Flowchart
Table 7-1	Subcontractors and Services
Table 8-1	Project Schedule

FIGURES

Figure 1-1	Vicinity Map
Figure 1-2	Site Plan
Figure 1-3	Aerial Map of Dam and Near Vicinity
Figure 2-1	Columbia River Dams
Figure 2-2	3-D Perspective View-Upstream
Figure 2-3	3-D Perspective View-Downstream
Figure 2-4	Sandblast Area and Catch Basin Outfalls
Figure 3-1	Landfill Footprint & Location of Groundwater Monitoring Wells
Figure 3-2	Sources of Sediment Contamination & Historical PCB Concentrations
Figure 3-3	Former Pile Locations
Figure 4-1	Grain Size Distribution & Observations
Figure 4-2	Human Health Conceptual Site Model
Figure 4-3	Ecological Conceptual Site Model
Figure 5-1	Proposed Sample Locations

APPENDICES

Appendix A	Technical Memorandum: Goose Island Construction History
Appendix B	Dredge Evaluations and Other Studies by USACE
Appendix C	Hydraulic Modeling Memorandum



REVISED DRAFT