
APPENDIX A

ENGINEERING APPENDIX

ENGINEERING APPENDIX

Index

Chapter 1	Columbia River Channel Navigation Analysis
Chapter 2	Mouth of the Columbia River Navigation Analysis
Chapter 3	Departure Delay Analysis
Chapter 4	Columbia River Stage Forecasting System analysis
Chapter 5	Existing Utility Crossings
Chapter 6	Geotechnical Information
Chapter 7	Benson Beach Disposal Site Evaluation
Chapter 8	Baseline Cost Estimate

CHAPTER 1

COLUMBIA RIVER CHANNEL NAVIGATION ANALYSIS

1.1. Introduction

The navigation practices of deep-draft vessels on the Columbia River influence the channel design and potential benefits of any channel improvement project. Especially important are the practices of container ships and bulk grain carriers that could take advantage of a deeper channel. The existing navigation practices are the product of the combined effects of river stages, channel depths, size, speed and scheduling of vessels, operating requirements of the pilot groups, and policies of the shippers and government regulators.

To define the navigation practices of container ships and bulk grain carriers on the Columbia River, a detailed study was made of transits that occurred in 1991 through 1993. The goals of the study were to identify the operating limits of ships that might benefit from a deeper Columbia River navigation channel. The study analyzed the number of transits, vessel drafts, departure timing, and underkeel clearances. Additional transit data from 1994 and 1995 was used to supplement the detailed analysis of vessel drafts. The results of the analysis were then presented to shippers and pilots for concurrence and/or refinement.

In the following discussions, the term "draft" will be used to refer to a ship's draft in the fresh water Columbia River channel. For ships with drafts in the range of 36- to 40-ft, the fresh water draft is about one foot deeper than the salt-water draft.

1.2. Navigation Database

To conduct the study of navigation practices, a large database was compiled for Columbia River transits that occurred from 1991 through 1993. Data collected included vessel characteristics, transit information, water surface elevations, and channel depths.

1.2.1 Vessel Transit Database

The Port of Portland compiled an extensive array of information on nearly 6,000 Columbia River vessel transits that occurred from 1991-1993. The data included vessel characteristics, routes, local port-of-call, arrival and departure times, freshwater sailing drafts, and cargo types and volumes. Data was obtained from the Columbia River Bar Pilots, Columbia River Pilots, Lloyd's Registry, Merchants Exchange, and PIERS.

1.2.2 Controlling Channel Depths

The controlling depths along the channel were determined from Corps of Engineer's 1991-1993 hydrographic surveys. Each navigation bar (approximately a 3-mile reach) was surveyed 6 to 10 times per year during that time period. The individual surveys along the river were examined to identify the maximum channel elevations a ship would experience as it moved through the channel. A high bottom elevation had to occur over 200-300 ft of the 600-ft wide channel before it was considered a controlling depth. Shoals along the edge of the channel were not considered to be controlling factors in navigation because ships have the ability to sail around them.

1.2.3 Water Surface Elevations

Observed water surface elevations were obtained from a series of six gages operated by the National Weather Service for the Port of Portland as part of a river stage forecasting system. These gages provide real time water surface elevations that are used in a river stage prediction computer model and can be used by Pilots to plan vessel departures. The gage locations and datum are:

Location	River Mile	Datum Elevation in Feet	
Astoria	18	0.00 MLLW	-3.07 NGVD
Skamokawa	35	0.00 CRD	-2.15 NGVD
Wauna	42	0.00 CRD	-1.76 NGVD
Longview	67	0.00 CRD	-0.34 NGVD
St. Helens	86	0.00 CRD	0.89 NGVD
Vancouver	106	0.00 CRD	1.82 NGVD

1.3 Navigation Practices Analysis

1.3.1 Vessel Draft Analysis

The first step in the navigation practices analysis was to identify which types of ships might benefit from a deeper navigation channel. The sailing drafts for inbound and outbound transits were reviewed for trends. As Figure 1 shows, outbound drafts are significantly deeper than inbound drafts. The difference between inbound and outbound drafts was expected because export tonnage far exceeds import tonnage on the river. It was determined that the navigation analysis would concentrate on the outbound navigation practices.

The nearly 1000 outbound transits with drafts over 36 ft were then examined to identify the type of cargo and the departure port. This examination identified three groups of ships that might benefit from a deeper channel. The three groups were; the panamax class bulk carriers that loaded corn from the Port of Kalama, bulk carriers that loaded wheat from elevators in Portland and Vancouver, and container ships that called at the Port of Portland. Discussions with shippers and pilots confirmed that those three groups of ships were most likely to benefit from a deeper channel.




Figure 1. Observed inbound and outbound drafts for all vessel types during 1991-1993. Both data sets have been sorted independently to plot from maximum to minimum.

The panamax class bulk carriers that loaded corn from the Port of Kalama had the deepest drafts. More than 150 of the 487 ships that departed Kalama had design drafts over 40 ft and 107 ships had sailing drafts of 40 ft or more. The deepest draft departing Kalama was 41.6 ft.

There were approximately 1200 bulk carriers that loaded wheat in Portland and Vancouver. Only 25 of those ships had outbound drafts over 39.9 ft, however there were over 460 ships with outbound drafts of 36 ft or more. The deepest outbound draft was 41.3 ft.

The final group was the 650 container ships that called at the Port of Portland. The design drafts for those ships were mostly 38 ft, with some ships having design drafts of 42 ft. Only 62 container ships had outbound drafts over 35.9 ft and only one had a 40-ft draft. Figure 2 shows the design, inbound, and outbound drafts for each container ship transit. The data has been sorted by outbound draft, and shows the corresponding inbound draft and the ship's design draft. As Figure 2 shows, a few container ships enter the river with drafts over 35 ft.




Figure 2. Design, inbound and outbound drafts of container ships transiting the Columbia River in 1991-1993. The data has been sorted to present the outbound drafts in descending order, with the related design and inbound drafts plotted at the same x-axis location.

1.3.2 Transit Modeling

To fully define navigation practices, it was necessary to determine the minimum depth of water and minimum underkeel clearance acceptable to the three groups of ships identified above. To evaluate those parameters, a computer model was developed to reproduce actual transits. The model used actual ship draft and sailing time, channel controlling depths, and observed river stage data to calculate vessel speed and squat, depths of water available and underkeel clearance. A total of 309 transits were reproduced, including 120 bulk carriers from Kalama and 112 bulk carriers from Portland/Vancouver, all the bulk carriers had outbound drafts of 38 ft or more. Ships over 38 ft draft were used because it incorporated most of the panamax class ships and those ships that were making the most use of the water depth available. For container ships, 67 ships with drafts of 35.5 ft or more were analyzed. These were the deepest draft container ships and all had design drafts over 38 ft.

The model used the sailing time from the port of departure to Astoria to compute the average vessel speed. The average speed was then used to compute the ship's squat (the sinkage of the stern of a ship as it moves through the water). Since squat is roughly proportional to the ship's speed squared, the faster container ships experience more squat than the slower bulk carriers.

River stages were interpolated from the hourly gage data and the timing of the transit. At the gage sites the stage during the transit was interpolated from the hourly stages bracketing the transit time. The river stages at locations away from the gage sites were interpolated based on timing and distance to the upstream and downstream gages. The stage was calculated at each navigation bar along the transit to produce a continuous water surface profile.

The total water depth available at each bar was calculated by adding the computed river stage, feet above or below CRD, to the controlling depth, in feet below CRD, taken from the channel surveys. The underkeel clearances were then the differences between the total water depth available at each bar, and the sum of the ship's draft and squat. Figure 3 shows typical results from the transit model. The results for each transit were then sorted to identify the minimum and maximum values for river stage, controlling depth, total water available, and underkeel clearance.




Figure 3. Vessel transit model results showing the reproduced water surface elevation, channel bottom elevation, total depth of water available, and underkeel clearance along the channel.

1.4 Operating Practices

A set of operating practices was defined for each of the three groups of ships likely to benefit from a deeper channel. Target values were identified for draft and minimum underkeel clearance. The target values were defined as the limiting values acceptable under normal operations. The values were initially identified from the transit modeling results and then confirmed during discussions with shippers and pilots.

1.4.1 Kalama Bulk Carriers

The bulk carrier fleet that calls at Kalama primarily loads corn. The fleet is comprised of two classes of ships, handy size vessels with design drafts of 30-36 ft and panamax class vessels with

design drafts of 40-44 ft. Because corn can be purchased and shipped in large lots, panamax class ships comprised about 40 percent fleet, as shown in Figure 4.

The bulk carriers that call at Kalama typically remain in the river for a week or more and attempt to load as much grain as possible before departing. The panamax ships will delay their departure to take advantage of the maximum water depth available to load more grain. However, as Figure 4 shows, nearly all of the panamax vessels left Kalama light loaded, while the handy size ships tended to sail at or over their design drafts.




Figure 4. Design and outbound drafts for bulk carriers calling at Kalama in 1991-1993.

Figure 5 shows that from 1991 through 1993, of the 120 ships with sailing drafts of 38 ft or more, 34 sailed with a 40-ft draft and 43 sailed with drafts over 40 ft. Forty-feet was initially selected as the target sailing draft from Kalama because it was the median draft for the panamax ships. Drafts deeper than 40 ft are possible but require better than average channel conditions. The 1994-1995 draft data supported a target draft of 40 ft as there were 46 ships with 40 ft draft and only seven over 40 ft.




Figure 5. Outbound draft and corresponding minimum underkeel clearance for the 120 ships that departed Kalama with drafts of 38 ft or more, in 1991-1993. The data has been sorted to present outbound drafts in descending order.

As shown in Figure 5, the minimum underkeel clearance was 0.0 ft or less on 33 of the modeled transits. The negative underkeel clearance values probably indicate, a limitation in the modeling method, the ship slowed to reduce squat or maneuvered around the shoal during the transit, or the ship actually touched bottom during the transit. The minimum underkeel clearance typically occurs only at one point along the channel, often just for 100-200 ft as the ship passed across the top of a single sand wave on the bottom of the channel. Because of the frequency of occurrence of 0.0 ft of underkeel clearance, limited potential for cargo damage, and the short duration of the event, 0.0 ft was selected as the target underkeel clearance for the panamax ships sailing from Kalama.

1.4.2 Portland/Vancouver Bulk Carriers

Grains, mainly wheat and barley are the main bulk cargoes exported from Portland and Vancouver. The grain fleet is comprised of both handy size and panamax class bulk carriers, as shown in Figure 6. Wheat constitutes the majority of the grain exports and is mainly shipped in handy size vessels. During 1991-1993, almost as many panamax class grain ships called at Portland/Vancouver as called at Kalama, however because of the size of the fleet, Panamax class ships made up only about 10 percent of the fleet.




Figure 6. Design and outbound drafts for bulk carriers calling at Portland and Vancouver in 1991-1993.

The bulk carriers that call at Portland and Vancouver typically remain in the river for a week or more and attempt to load as much grain as possible before departing. The handy size ships tended to sail at 33-35 ft drafts, often 2-3 ft over their design drafts. To maximize cargo tonnage, the panamax ships often scheduled their departure to take advantage of the maximum water depth available. However, as Figure 6 shows, nearly all of the panamax vessels sailed light loaded.

A target draft of 39 ft was selected for the Portland/Vancouver panamax size grain ships. Figure 7 shows that in 1991-1993, 39 ft was the median draft of grain ships with drafts over 38 ft. In 1994-1995 there were 139 ships with drafts of 38 ft or more, and the median draft remained 39 ft. This target draft is 1.0 ft less than that identified for Kalama, for the same type of ships. The difference in target drafts is probably due to more limiting channel conditions during the longer transit from Portland/Vancouver. Ships from Portland/Vancouver pass through two low water surface points in the channel, while ships from Kalama only need to pass through one low water point. The longer transit also increases the likelihood of encountering a shoal.




Figure 7. Outbound draft and corresponding minimum underkeel clearance for the 112 ships that departed Portland and Vancouver with drafts of 38 ft or more, in 1991-1993. The data has been sorted to present outbound drafts in descending order.

The minimum underkeel clearance analysis results in Figure 7 show a trend very similar to that of the Kalama analysis, with 24 model runs resulting in zero or negative values. For the reasons given in the above Kalama discussion, 0.0 ft was also selected as the target minimum underkeel clearance for Portland/Vancouver bulk carriers.

1.4.3 Portland Container Ships

Container ships operate much differently than the bulk carriers. They are schedule driven and only make short, 1-2 day, calls in the Columbia River as part of an Asia-North America route. Container ships must be able to arrive and depart on set schedules, without delaying for low river stages. Portland is the last North American port-of-call for many container ships. Those ships could be expected to load as much cargo as possible and sail at or near their design drafts. However, the container ships are also concerned about underkeel clearance, because they carry cargo that is fragile and of high value.

As shown on Figure 2, the vast majority of container ships have design drafts around 38 ft, with a few larger 41-42 ft draft ships. The departure drafts show a clear break in slope at 36 ft. This break does not correspond to a change in ship size as it did for the bulk carriers and was interpreted as a change in operating practices by the container ships. The 36-ft draft was

therefore selected as the target draft for container ships. In discussions with shippers it was confirmed that 36 ft was their target draft because they could depart at any time without being delayed by a low river stage.

Because of the schedule that container ships are on, few of them try to make full use of the available water depth. In general, the container lines plan to have available on the dock the maximum amount of cargo that can be loaded onto the vessel within the scheduled loading time. However, they do not normally load more than the target draft, even if there are time and cargo available. Only 35 of 649 container ships had departure drafts over 36 ft during the 1991-1993 period. The container traffic increased significantly in 1994-1995 and 157 ships, out of 560, had drafts over 36 ft. In 1994-1995 one container line operated a group of panamax size ships that regularly sailed with drafts in the 38-40 ft range. The container line consulted with the Columbia River Pilots to schedule departure times, sometimes delaying a ship's departure, to take advantage of the maximum water depths available.

As Figure 8 shows, of the 67 container ship transits modeled, only 5 had calculated minimum underkeel clearances of less than zero. There were 17 ships with minimum underkeel clearances of less than 2.0 ft. Two feet was chosen as the target minimum underkeel clearance since that value was exceeded by 75 percent of the 67 deepest container ships. This value fit well with the general container ship guideline of a 4-5 ft allowance for squat and underkeel clearance.




Figure 8. Outbound draft and corresponding minimum underkeel clearance for the 67 container ships that departed Portland with drafts of 35.5 ft or more, in 1991-1993. The data has been sorted to present outbound drafts in descending order.

CHAPTER 2 MOUTH OF THE COLUMBIA RIVER NAVIGATION ANALYSIS

2.1 Introduction

This analysis of navigation at the mouth of the Columbia River (MCR) was made to determine the compatibility of the existing 55-ft entrance channel with the proposed 43-ft river channel. Specific issues are whether MCR would have to be deepened to handle the 43-ft draft ships expected in the proposed river channel and to estimate potential delays those ships might experience, at MCR.

2.2 Background

The navigation channel at the mouth of the Columbia River (MCR) is a tiered channel, with the north side being 55 ft deep by 2000 ft wide and the south side being 48 ft deep and 640 ft wide. The 55 ft depth was intended to optimize the operations of the 40-ft Columbia River navigation channel. Improvement of the MCR is not part of the current channel deepening study. Therefore, it is necessary to determine if deeper draft ships might experience delays due to depth limitations at the MCR.

The Interim Feasibility Study and Final Environmental Impact Statement for the 55 ft MCR channel were completed in March 1983. The project design was based on the results of the "Columbia River Entrance Channel Deep-Draft Vessel Motion Study" (VMS) completed by Tetra Tech, in September 1980. The VMS measured heave, roll, and pitch, to determine the vertical excursions of 53 ships, over a two-year period. A correlation was developed between wave height and vessel excursion that accounted for varying wave and vessel characteristics.

2.3 MCR Design

The MCR design criteria was for a 36-ft fresh-water (FW) draft vessel to be able to transit MCR 95/0 of the time during "safe" wave conditions without exceeding the design excursion. Safe wave conditions were defined as waves less than 10 ft high, a condition that occurred 95% of the time according to the wave forecast used in the design. The design excursion was then defined as the value for which 95% of the excursions during 95% of the transits would not be exceeded. The resulting design conditions were as follows:

<u>FW Draft (ft)</u>	<u>Design Excursion (ft)</u>	<u>MCR Depth (ft)</u>	<u>Min. Tide Stage (ft)</u>	<u>Max. Wave Height (ft)</u>
36	16.5	55	0	8 (est.)
40	16.8	55	4	8 (est.)

As a comparison, on 7 of the 53 VMS transits the wave heights exceeded 10 ft and maximum downward excursion exceeded 20 ft on 6 VMS transits.

Given the above MCR conditions, a 55-ft deep MCR would be open to 36-ft FW draft ships 89% of the time and to 40-ft FW draft ships 44% of the time, based on combining the wave height and tide stage frequency curves used in the design report. Stated another way, the bar could be expected to be closed for 960 and 4900 hours each year for 36- and 40-ft drafts respectively.

2.4 Bar Pilots Operating Practices

As standard operating practices, the Columbia River Bar Pilots have two factors related to physical conditions in the river and entrance that limit transits on the MCR. The primary limitation is the underkeel clearance in the river channel between RM's 6 and 13. This restricts the draft and departure time of some deep-draft ships. The second limitation is the wave conditions at MCR, which can close the bar and prevent a ship from departing.

2.4.1 Underkeel Clearance Requirements

The minimum underkeel clearance in the river channel downstream of Astoria is normally the controlling factor for draft and time of departure. The standard operating practices for minimum underkeel clearance are; 4 ft on a falling tide, and 3 ft on a rising tide at Astoria. These are safety clearances and do not include allowances for squat. Squat is kept to a minimum by sailing at low speeds. The safety clearances are the same for both bulk and container ships. These, underkeel clearances do not correspond to a specific draft limitation because they are a combination of ship draft, controlling channel depth, and tide stage. Ships with 36-ft or less FW draft can meet the underkeel requirements essentially anytime, but about half the 40-ft FW draft ships must delay their upriver departures to wait for suitable tide stages.

The deeper draft ships time their departures from the upstream ports so their arrival at Astoria coincides with the required tide conditions. If a ship delays to wait for the tide, the ship must delay its departure from the upstream port, as there is no place to stop and anchor in the estuary. Only in an extreme case, such as a sudden storm, would a loaded ship be stopped and anchored in the estuary after departing an upstream berth.

2.4.2 Bar Closures

The standard practice for determining bar closures is for the individual pilot to decide if the wave conditions are unsafe either for the pilot boat or the ship scheduled to transit MCR. The bar is generally closed when there are breaking waves in the entrance. However, for less severe wave conditions the pilot must decide on the safety of a transit based on the characteristics of the ship and the waves.

The bar pilots do not differentiate based solely on a ship's draft when deciding on the safety of an MCR transit. A ship's ride and steering characteristics are also important factors in deciding the

risk of a transit. The draft, length, beam, type and location of cargo, and hull design can all influence the ride and steerage of a ship.

Pilot experience has shown that ship length is an important factor in determining ship handling across MCR. Ships of around 600 ft in length experience large amounts of plunge because of the way they interact with the short wave lengths present at MCR. The longer, deeper-draft Panamax ships have significantly less plunge because their length dampens the wave effects. The reduced plunge offsets the deeper draft and results in less total penetration for the longer ships. However, rolling becomes more of a concern with the larger ships.

2.5 Regulatory Environment

The maximum draft on the Columbia River may be more a function of government regulation than physical parameters. The regulatory environment at the Oregon Board of Maritime Pilots tends to hold pilots at fault for any incident with a ship drawing over 40 ft, regardless of the circumstances. Given the potential risk of losing their license, bar and river pilots are hesitant to pilot ships over 40 ft draft available to do in the existing channel even if there were sufficient water depths so.

2.6 Observed MCR Operations

The available data on MCR transits was reviewed to determine historical practices. The total length of bar closures and transit drafts were reviewed for the time period 1961 to 1995. Also departure stage and tide condition data from 1991 through 1993 were examined. Data provided by the Bar Pilots showed the total length of time that MCR was closed each year declined steadily between 1961 and 1987, Figure 1. While over the same time period, the deepest drafts transiting MCR increased from 33-ft to 40-ft (FW draft).




Figure 1. Hours of bar closure and maximum draft of ships transiting MCR each year since 1961.

In 1964, with a 35-ft river channel and 48-ft entrance, the 4-year average for bar closures was 350 hours per year and the deepest drafts were around 33 ft. In 1971, with a new 40-ft river channel and a 48-ft entrance, the bar was closed an average of 275 hours per year and drafts had increased to around 36 ft. By 1981, just prior to deepening the entrance, the bar closures had decreased to a 4-year average of only 105 hours per year and drafts increased to 38-ft. After deepening the entrance to 55-ft, bar closures fell to an average of near 50 hours per year and the deepest drafts increased to 40 ft.

There are clear trends of declining closure time and increasing drafts. However, the two trends may not be directly related to the depth of the MCR channel. New pilot boats received in 1967 and 1977 improved the pilot's ability to cross the bar in bad weather and contributed to a 70% decline in annual closure time between 1961 and 1981. This decline in closure time occurred without deepening the entrance channel and despite increasing ship drafts. Since 1984, the deeper MCR channel and longer ships were factors in reducing average annual closure time to only 50 hours.

The increases in draft seen at MCR resulted from numerous factors occurring both locally and globally. The global trend to deeper draft ships has been underway for many years and was facilitated locally by deepening the river channel in 1972 and the entrance in 1984. The establishment of the Peavy corn terminal in 1983 brought a fleet of larger ships that caused an increase in the number of ships drawing 40-ft or more. In recent years the increasing size of container ships has also contributed to the increase in 39- to 40-ft draft ships.

The development of the Loadmax stage forecasting system for the Columbia River in the mid-1980's allowed pilots to increase drafts by making better use of the available water depths in the river. It has also helped river pilots plan transits so they can meet the bar pilot's underkeel requirements. Of the 300 deepest draft ships that transited the Columbia River during 1991 through 1993, only about 10% did not meet the bar pilots' underkeel clearance guidelines.

Breaking waves, a hazard to both the pilot boats and commercial ships, are the most common reason for closing the bar. Breaking wave conditions are most severe during the few hours of strong ebb currents within a tidal cycle. However, during the last 10 years the average length of closure has been about 13 hours (1/2 a tide cycle) and the longest ranged from 20 to 36 hours. This suggests that closures are caused by a few large storms that generate high waves for extended periods of time.

2.7 Comparison of Actual vs. Design

There are several puzzling inconsistencies apparent when the 1983 MCR design parameters are compared to actual occurrences. These include the "safe" wave height and total length of closure, the assumed relationship between vessel draft and bar closure, and the expected excursion.

2.7.1 Wave Closures

The first inconsistency is under what wave heights ships will transit MCR. The design report assumed 10 ft as the maximum "safe" wave height that ships would transit. The design data indicated this would be exceeded 50/6 of the time or nearly 440 hours per year. Even during the 10 years before the MCR deepening the bar was generally closed only 100 to 150 hours per year, with a maximum of 300 hours in 1977. Since the MCR deepening, closures have been between 25 and 140 hours per year, far less than might be expected given the "safe" wave height criteria. It seems obvious that ships can and do transit MCR during higher than 10 ft waves. This was even documented in the VMS data that included transits with wave heights of up to 20 ft.

Another comparison of closure conditions was made by selecting two specific years, 1984 and 1992, to see how wave heights and closure times compared to the design assumption. Data from the Bar Pilots indicate that MCR was closed for 25 and 30 hours in 1984 and 1992 respectively, while wave heights exceeded 10 ft for 20% (1750 hours) and 10% (875 hours) of those years, respectively. The wave height/frequency data from 1984 and 1992 suggests that MCR is only closed when wave heights exceed 18-19 ft, which is more consistent with the VMS wave data and the recent annual closure durations.

2.7.2 Draft vs. Closure

The second inconsistency has to do with the bar being closed to some ships but not to others. The 1983 MCR design report predicted that for a given wave height, downward penetration would increase with increasing draft. Therefore, under certain wave conditions, ships with 36-ft draft could cross the bar when 40-ft draft ships would have to wait for higher tide stages to cross. However, experience has shown that the bar is open or closed on a ship by ship bases, with draft being only one of several determining factors.

While the deeper draft ships do frequently transit MCR during high tide, it is because of the underkeel clearance requirements within the river channel and not because of MCR wave conditions. The Bar Pilots' experience with deeper draft ships crossing MCR has shown that they handle better and have less excursion than the shallower draft ships. This runs counter to the findings of the VMS that showed slightly more excursion for the deeper ships. The variance is probably due to the similarity in length of the deeper and shallower draft ships in the VMS, and the greater length of the 40-ft draft ships currently calling on the river.

2.7.3 Excursion

The third inconsistency has to do with how much excursion a ship might experience. A wave height of about 8 ft with an excursion of 16.5 ft was used as the design values for the 55 ft entrance depth. During the VMS, measured excursions exceeded the design excursion by over 4

ft for similar wave conditions. There were also transits that occurred under much higher wave conditions that had excursions up to 9 ft deeper than the design value.

Since both excursion and wave height could exceed the design values, the risk of ships hitting bottom at MCR appears to be much higher than anticipated. Despite the apparent higher risk, there have been no reports of problems with ships hitting bottom at MCR. This suggests that there is less excursion, deeper water, or both at MCR than expected during the design.

The smaller than expected excursion experienced by the long, 40-ft draft ships could account for some of the lack of grounding, but does not explain why shallower ships are not hitting bottom. Changes in hull design and wider beams may have resulted in a reduction in the excursion for some of the shallower draft ships. There is also some speculation that ships may not ground because they are hydraulically cushioned as they near the bottom.

The hydrographic surveys consistently show bottom elevations deeper than 55-ft over most of the entrance channel. Pilots can follow the deep-water channel and gain extra underkeel clearance. The channel reach most exposed to high waves is from RM -2 to RM 0. This reach typically has controlling depths of 58-60 ft, providing an extra 3 to 5 ft of clearance. Ships may also be penetrating a portion of the 2-ft underkeel clearance safety zone. Based on the design assumptions, an extra 3 ft of depth plus 2 ft of underkeel clearance would allow ships to transit under wave conditions just 3 ft higher than the design values.

It appears that for MCR to be open an average of over 99% of the time, downward excursions must be less than originally estimated. This conclusion applies to ships with 34-ft drafts as well as those with 40-ft drafts. This is a critical safety issue that needs to be more clearly defined.

2.8 With Project Operating Practices

The Bar Pilots expect the with project operating practices to be very similar to the current practices. Since the underkeel clearance in the channel is normally the limiting factor, the 43-ft channel should allow 43 ft draft ships to transit the Astoria reach during higher tide stages. The Bar Pilots are confident that MCR can handle 43 ft draft ships without significant delays. There is a likelihood that the Pilots will initially be cautious with the deeper drafts, resulting in some small increase in delays over those currently experienced by 40 ft draft ships, but this is not expected to last long or to be significant.

Based on the excursion analysis done for the MCR deepening, 40 ft FW draft ships should be delayed because of wave conditions nearly 10% of the time. However, the historic record does not support this level of closure. Until the discrepancy between the theoretical results of the design report and actual operations can be explained, the actual operations must be used as the guide on the level of closures that can be expected,

The institutional constraint on maximum draft in the Columbia River is related to the authorized channel depth. This constraint applies to the Bar Pilots because their pilotage includes a 10-mile reach of the river channel, approximately from CRM 3 to CRM 13. This reach would be

deepened as part of the proposed deepening project. It is assumed that deepening this reach to 43-ft would shift the regulatory environment at Oregon State Board of Maritime Pilots to allow a maximum draft of 43-ft at the MCR.

2.8.1 Delays

Given the conflicting information on excursions and bar closures, there is much uncertainty in future MCR operations with a 43-ft river channel. Bar closures appear to be determined by the presence of breaking waves that make the bar unsafe for the pilot boats and commercial ships. MCR closures have been insignificant during the last 10 years, averaging only about 50 hours per year. Since this trend is not directly related to ship drafts, it can be expected to continue after the completion of the 43-ft river channel.

The Bar Pilots are expected to continue their requirement for minimum underkeel clearance downstream of Astoria of 4 ft on a falling tide or 3 ft on a rising tide. This will result in delays for 41- to 43-ft FW draft ships similar to those now experienced by 38- to 40-ft FW draft ships. Those delays are listed on the following table.

<u>Draft</u>	<u>Available Transit Time per Tide Cycle</u>	<u>Delay Time per Tide Cycle</u>	<u>Avg. Time per Delay</u>	<u>Probability of Delay</u>	<u>Avg. Delay per Ship</u>
43 ft	13.6 hrs	11.2 hrs	2.8 hrs	45%	1.3 hrs
42 ft	16.4 hrs	8.4 hrs	2.1 hrs	34%	0.7 hrs
41 ft	20.0 hrs	4.8 hrs	1.2 hrs	19%	0.2 hrs

2.8.2 Recommended Analysis

Since the MCR is expected to continue to be closed on a ship by ship basis, there is a need to refine the wave height, expected excursion and the level of risk of hitting bottom for wave conditions just below the breaking wave level. Given the potential consequences of hitting bottom, it seems like the design should be based on E95 or higher, of the extreme excursion values. The 1983 design failure rate of 5% leaves the potential for some ships to hit bottom up to 10 times during a single transit. The expected and actual excursions both need to be reviewed before the channel design is finalized.

CHAPTER 3 DEPARTURE DELAY ANALYSIS

3.1 Introduction

River pilots of ships with drafts in the 38- to 40-ft range must schedule their departures to meet underkeel clearance requirements within the Columbia River channel and at the mouth. This can require ships to delay their departure from upriver ports for several hours after they have finished loading to wait for favorable tide conditions. The length of a delay depends on the ship's draft, river discharge, tide stages, and controlling depths in the channel.

3.2 Operating Practices

Ship transits on the Columbia River are governed by a number of standard operating practices that are influenced by the pilots, vessel type, tide stages, wave conditions, controlling depths, and government regulators. While there have been exceptions to any and all of the following practices, the standard operating practices for the Columbia River are described below.

The designated 40-ft depth of the navigation channel is based on a low-low-water, water surface profile referred to as the Columbia River Datum (CRD). The actual depth of water available in the channel during any given transit depends on the combination of tide, river discharge and controlling depths. Each of those parameters is constantly changing, with tide stage being the critical factor on a day-to-day basis. By taking advantage of tide stages that are frequently 1- to 2-ft or more above 0 CRD and controlling depths greater than 40 ft, a ship may be able to transit with a minimum water depth of 42 to 45 ft.

Underkeel clearance is the critical factor for determining the departure draft of a ship transiting the river channel. Underkeel clearance changes constantly as a ship moves through the river because of the changing river stages and sand waves on the bottom of the channel. Minimum underkeel clearance generally occurs within a short reach of channel near the point of minimum river stage. Because of the limited duration of the condition, minimum underkeel clearances are quite small in the Columbia River. As explained in Chapter 1 of this Appendix, bulk carriers drawing 40 ft are willing to transit with a minimum underkeel clearance of 0 ft, while container ships prefer a minimum of 2 ft.

Tide and wave conditions at MCR also influence operating practices. The Bar Pilots standard practice is for a ship to have a minimum of 3 ft of underkeel clearance on a rising tide or 4 ft on a falling tide. This means that the river pilots of 39-40 ft draft ships must schedule their arrival in Astoria to fall within one of the two daily tide windows for MCR departure, as well as meet underkeel requirements in the river channel. High waves are not usually a factor in departure scheduling. However, waves in the range of 18-20 ft or higher, will close MCR to all ships.

The above minimum values for underkeel clearance and water depth available in the Columbia River would occasionally allow maximum drafts of 43 ft for bulk carriers and 42 ft for container ships. However, regulatory pressure from the Oregon Board of Maritime Pilots limits the maximum draft in the river to 40 ft.

These standard operating practices provide the basis for the delay times presented in the following sections. The expected delay for any given ship could be minimized by agreement between the shipper, and river and bar pilots to work outside of the standard practices.

3.3 MCR Delays

The Bar Pilots guideline is for a ship to have 3 ft of underkeel clearance on a rising tide or 4 ft on a falling tide. This means that 39-40 ft draft ships have two tide windows through which to depart MCR. How closely this is followed depends on the individual pilot and the channel conditions at the time of departure. However, because it is the most likely operating practice, that guideline was used to determine the potential delay times that could be attributed to MCR.

The following steps were followed to calculate delay times.

1. The controlling depth was assumed to be 40 ft CRD for the existing channel and 43-ft for the new channel.
2. The required tide stage was determined for the selected drafts.
3. The percent of the time that river stages would be below the required stage was determined from a stage duration curve for 1991-1993.
4. The total time during a tide cycle when stages were below the required level were divided into two equal periods.
5. Delays could range from 0 to 100 percent of a delay period, and would average 50 percent.
6. Since ships could be ready to depart from port at any time, the probability of a delay would equal the percent of time the tide stages were below the required level.
7. The average delay per Columbia River transit would then be equal to the average delay time multiplied by the probability of being delayed.

Draft in		Available		Avg. Time per Delay	Probability of Delay	Avg. Delay per Ship
40-ft Chan.	43-ft Chan.	Transit Time per Tide Cycle	Delay Time per Tide Cycle			
40 ft	43 ft	13.6 hrs	11.2 hrs	2.8 hrs	45%	1.3 hrs
39 ft	42 ft	16.4 hrs	8.4 hrs	2.1 hrs	34%	0.7 hrs
38 ft	41 ft	20.0 hrs	4.8 hrs	1.2 hrs	19%	0.2 hrs

3.4 River Delays

In order to meet the Bar Pilots requirements at MCR, ships must pass through a low tide somewhere within the river channel. The river pilot can adjust departure time to sail through that low tide at a location with sufficient controlling depth to maintain an acceptable amount of underkeel clearance and still meet the bar pilot's requirements.

The following delays are based on work done by Ogden Beeman and Associates in 1994 for the Port of Portland. Departure drafts have been adjusted from the Beeman work to account for the different minimum underkeel clearance requirements of bulk carriers and container ships.

Container Ships

Draft in		Probability of Delay by Time Increment				Average Delay Per Transit
40-ft Chan.	43-ft Chan.	Time Increment of Delay				
		0 hrs.	0-6 hrs.	6-12 hrs.	12-24 hrs.	
40 ft	43 ft	44%	25%	14%	17%	5.1 hrs.
39 ft	42 ft	73%	21%	6%	0%	1.2 hrs.
38 ft	41 ft	100%				0 hrs.

Bulk Carriers

Draft in		Probability of Delay by Time Increment				Average Delay Per Transit
40-ft Chan.	43-ft Chan.	Time Increment of Delay				
		0 hrs.	0-6 hrs.	6-12 hrs.	12-24 hrs.	
41 ft	44 ft	44%	25%	14%	17%	5.1 hrs.
40 ft	43 ft	73%	21%	6%	0%	1.2 hrs.
39 ft	42 ft	100%				0 hrs.

The delays for MCR and the river are not additive because the river delays are scheduled to meet the MCR sailing windows. The delay that a ship would experience would be the longer of the MCR or river delays.

CHAPTER 4 COLUMBIA RIVER STAGE FORECASTING SYSTEM ANALYSIS

4.1 Introduction

The demands of world trade place constant pressure on shippers and pilots to transit the Columbia River at deeper drafts. As a result, the Corps of Engineers and the seven Lower Columbia River ports are currently conducting the Columbia River Channel Improvement Feasibility Study to evaluate potential navigation channel improvements. An early finding of that study has been that many of the deepest draft outbound ships are not now taking full advantage of the water depths available in the existing 40-ft navigation channel.

Improvements to the existing river stage forecasting system, commonly referred to as "Loadmax", could allow ships to increase their drafts by providing better forecasts of the water depths available. An improved forecasting system could be implemented and operating in a short period of time. This report summarizes the existing navigation practices and forecasting system, the improvements that could be made to the forecasting system, and the potential benefits to shippers.

4.2 Background

The Columbia River navigation channel is currently authorized and maintained at the depth of -40 ft Columbia River Datum (CRD), from the mouth upstream to River Mile (RM) 105.5 (Figure 1). However, because the CRD is a low-low-water datum, ocean tides produce river stages that are above 0 ft CRD over 90 percent of the time (Figure 2). Figure 3, shows how the channel depth and stage combine to provide the water depth available for a transit.

For many years, the Columbia River pilots have taken advantage of high river stages to move deep-draft ships through the river. Prior to 1984, they relied on their own experience with the river to guide them in selecting safe drafts. In 1984, the Port of Portland, Portland District Corps of Engineers, National Weather Service, and National Ocean Service determined a need to develop an hourly river stage forecast and a real-time river stage monitoring network for the Columbia River deep-draft navigation channel. The Northwest River Forecast Center (NWRFC) created an interactive dynamic wave computer model, capable of providing a three day, hourly stage forecast for the six sites along the channel shown on Figure 1. The three day forecast allowed pilots and shippers to plan departure times to make better use of higher river stages to increase safe vessel drafts on the river. In 1988, NWRFC extended the forecast period to six days.

4.3 Forecasting System Limitations

The analysis of standard operating practices for 1991-1993 (Chapter 1 of this Appendix) found that while maximum drafts had increased to over 41-ft for bulk carriers and to 40-ft for container ships, the water depths available were not consistently being fully utilized. Ships are routinely limited to the predetermined target drafts listed in Chapter 1. However, Figures 4, 5, and 6 show that both bulk carriers and container ships sailing at their respective target drafts commonly had underkeel clearances that ranged from 1-ft less to 4-ft greater than the minimum acceptable clearances. Bulk carriers occasionally may touch bottom on shoals with bed elevations above 40 ft CRD project depth. This does not seem to be a serious problem, but is a safety concern. The range of underkeel clearances indicates there are opportunities to increase both draft and safety for the deepest draft transits on the Columbia River.

It appears from Portland District's analysis of Columbia River navigation practices, that the existing river stage forecasting system is not providing an adequate forecast for shippers to make optimum use of water depths available.

A few general comments were made about the reluctance of some shippers to rely on the forecasts, but no specific explanation of its limitations came out during discussions with shippers or pilots in 1995. The Corps' own analysis suggests four main limitations in the existing river stage forecasting system:

1. Concern about the accuracy of the river stage forecast.
2. The forecast may not extend far enough into the future to allow container lines to adjust cargo schedules to take advantage of opportunities for greater than minimum available water depths.
3. Navigation channel shoal conditions are not included in the forecast, therefore the comprehensive water depth available is not being provided.
4. The river level forecast is presented in a tabular form that does not give a clear picture of expected river conditions, and may be difficult to understand for someone unfamiliar with the Columbia River.

Container ships that have design drafts of 38- to 41-ft are currently targeting a draft of only 36-ft. The container lines are concerned about the reliability of service, therefore they schedule only enough outbound cargo to be at the docks to load to a predetermined draft. To be useful to the container lines, the river stage forecast must provide reliable data far enough in advance to allow cargo scheduling to maximum drafts.

Bulk carriers use more of the water depth available to them than the container ships, but they still do not make maximum use of the water depths available. Bulk carriers with 40- to 41-ft drafts currently delay their departures for several hours to take advantage of higher river stages. To maximize their drafts and avoid touching bottom, bulk carriers need forecast and observed data available to them right up to their time of departure. The most recent shoaling conditions are also valuable to bulk carriers because of the zero underkeel clearance at which they may transit.

4.4 THE PROPOSED SOLUTION

The existing river stage forecasting system could be greatly improved upon. Providing a more detailed forecast, in a user-friendly format can solve limitations 2, 3, and 4 above, relatively easily. Concerns about the accuracy of the forecast can also be addressed, but will take longer to resolve.

The procedures used by Portland District to analyze deep-draft navigation practices can be adapted to provide forecasts of not only river stages, but also water depth available and estimated underkeel clearance. Updated one- or two-dimensional hydraulic models could be used to improve the accuracy of the river stage forecast. The controlling shoal elevations for each reach of the channel would come from Corps of Engineers' hydrographic surveys and can be updated at approximately three-month intervals. The resulting forecast could then present total water depths available along the channel for a scheduled transit, in a user friendly, graphical format.

The entire forecast could be computerized so those forecasts could be obtained in a few minutes. The Pilots and shippers could enter a desired departure time and sailing draft, and view the forecast river stages, current shoal conditions, and water depth available all along the river for the transit. The point of minimum water depth available could be located and last minute changes made to departure time or vessel speed to optimize draft and safety. The current six-day forecast could be extended if necessary for better container cargo scheduling.

The accuracy and reliability of the forecast could be enhanced through improved hydrodynamic computer modeling and monitoring of forecast results. A monitoring program could compare the actual river stages at the six stage measurement sites to the forecast stages. The results of that monitoring could be provided to the users and also used to improve the hydrodynamic model.

4.5 THE BENEFITS

Implementation of the proposed improved forecasting system would provide shippers better opportunities to take full advantage of the water depths available. The full benefits to shippers are difficult to estimate, but an immediate 1-ft increase in the target drafts for containers and bulk carriers seems achievable. Figures 4, 5, and 6 give an indication of the potential draft increases that could have been gained by the ships included in the Corps' navigation practices analysis. Those figures indicate that about half the time, the deepest draft ships in 1991-1993 could have gained from 1- to 3-ft of outbound draft. With a more reliable extended forecast, container lines would frequently be able to fully load their 38-ft draft ships that make up the majority of the existing container fleet.

Increased safety will be an additional benefit of including shoaling conditions in the forecast. The negative underkeel clearances that were found during our analysis often occurred at shoals that had reduced channel depths to 37- to 39-ft CRD. These locations can be seen on the forecast plots and drafts or departure times adjusted to avoid undesirable conditions.


4.6 RECENT IMPROVEMENTS

Over the last two years (1998-1999), and as part of a national modernization effort, the NWS-NWRFC has made significant improvements to its hydrologic and hydraulic modeling that underlie the LoadMax system. At the same time, the River Forecast Center has implemented advanced technology in weather forecasting which is a key component of Columbia River flows. Additionally, the Port of Portland has installed technology at its river gauges to allow the pilots to call ahead from the vessel's bridge to obtain real-time river level information. The Port has also improved and automated the electronic delivery of the forecast data to the commercial users and research institutions who utilize the information on a regular basis.

The NW River Forecast Center estimates that the current accuracy of the LoadMax forecast is 0.3-0.4 feet for the first 24 hours, increasing to 1.0-1.4 feet for the 6th day (the current forecast limit). A longer-range forecast might allow container lines to schedule cargo to take advantage of potential higher river stages, however there would be even more uncertainty in the river stage forecast.

4.7 CONCLUSION

Continuous improvement of LoadMax is an important priority for the ports, river and bar pilots, the NW River Forecast Center, and steamship line customers that utilize the projected and real-time tide and river-stage information system. Recent enhancements have improved the LoadMax forecast and data distribution. Future upgrades, including the addition of bathymetric information, are being planned. It is estimated that future improvements to the river stage forecast system would be implemented as part of the day-to-day operations.



RIVER LEVEL REPORTING SYSTEM

River Level Gauging Stations

Figure 1

Stage Duration Curves
Columbia River LOADMAX Stations
1991-1993 Data





Figure 2



The total water depth available to a ship transiting the Columbia River is the sum of the channel elevation below Columbia River Datum (CRD) plus the river stage above CRD. The total depth of water required by a ship is the sum of its draft plus squat plus underkeel clearance.

Figure 3

COLUMBIA RIVER NAVIGATION

KALAMA BULK CARRIERS W/40.C FT DRAFT




Figure 4

COLUMBIA RIVER NAVIGATION

PORTLAND/VANCOUVER BULK CARRIERS W/ 38.5 - 39.5 FT DRAFTS




Figure 5

COLUMBIA RIVER NAVIGATION

PORTLAND CONTAINER SHIPS W/35.8 - 36.1 FT O/B DRAFTS




Figure 6

CHAPTER 5 EXISTING UTILITY CROSSINGS

1.1 INTRODUCTION.

1.11 General. A study of the existing utilities crossing the Columbia River (RM 0 to RM 105.5) and the Willamette River (RM 0 to RM 11) was undertaken to determine impacts from lowering the Columbia River Channel from the existing 40-foot depth to a 43-foot depth (48-foot depth overexcavation along the lower Columbia River and 45-foot depth overexcavation along the Willamette River).

1.12 Available Information. Available information to determine CRCD impacts to existing utility crossings included review of available regulatory permits; review of cable and pipeline crossings included in the Columbia River Maintenance Disposal Plan, September, 1991; and phone interviews with utility owners.

1.2 COLUMBIA RIVER UTILITY CROSSING'S (RM 0 TO RM 105.5).

1.21 General. Areas between the following river miles will require dredging to reach a channel depth of 43-feet:

- (1) RM 6 - 49
- (2) RM 50.5 - 52.5
- (3) RM 56 - 101
- (4) RM 102.5 - 105.5

1.22 Existing Utility Crossings. Existing utility crossings for the Columbia River are included in Table 1. A summary of those utility crossings being impacted by lowering the channel are shown below:

(1) RM 6.5, US Coast Guard, Four conductor telephone cable between Pt Adams (OR) and Chinook Point (WA), Located @ 45 feet below mean low low water (MLLW).

(2) RM 13.7, Pacific Telephone & Telegraph (US West), Cable crossing between Astoria (OR) and Point Ellice (WA), Depth of cable unknown.

(3) RM 14.5, Pacific Telephone & Telegraph (US West), Cable crossing between Astoria (OR) and Knappton (WA), Depth of cable unknown.

(4) RM 105.5, Spokane, Portland & Seattle Railroad (Burlington Northern), Communication cable crossing under railroad bridge between Hayden Island (OR) and Vancouver (WA), Depth of cable @ 40 feet below the low water line.

(5) RM 105.5, Northwest Natural Gas Company, Six-inch diameter pipeline located under railroad bridge between Hayden Island (OR) and Vancouver (WA), Depth of cable @ 44 feet below the low water line.

1.3 WILLAMETTE RIVER UTILITY CROSSING'S (RM 0 TO RM 11).

1.31 General. The area between RM 0 and RM 11.5 (Broadway Bridge) will require dredging to reach a channel depth of 43-feet:

1.32 Existing Utility Crossings. Existing utility crossings for the Willamette River are included in Table 2. A summary of those utility crossings being impacted by lowering the channel are shown below:

(1) RM 3.5, Portland General Electric, Power cable crossing to Rivergate Industrial Park, Depth unknown.

(2) RM 5.8, Pacific Telephone & Telegraph (US West), Communications cable crossing near the St. John's Bridge, Depth @ 43 feet below low water.

(3) RM 5.9, Portland General Electric, Power cable crossing near the St. John's Bridge, Depth unknown.

(4) RM 7, Spokane, Portland & Seattle Railroad (Burlington Northern), Located under railroad bridge, Four armored communication cables from south side of river and three cables from the north side of river, Depth @ 42 feet below low water.

(5) RM 11.25, Pacific NW Bell, Three communication cables, Depth @ 42 feet below low water.

(6) RM 11.25, Pacific Power and Light (PP&L), Cable crossing, Depth @ 37 feet below low water.

(7) RM 11.25, Pacific Power and Light (PP&L), Six 15KV transmission cables and one communication cable, Depth @ 42 feet below low water.

(8) RM 11.6, Portland General Electric, Power cable crossing under the Broadway Bridge, Depth unknown.

(9) RM 11.6, Pacific Telephone & Telegraph (US West), Six communication cables under the Broadway Bridge, Depth @ 43 feet below low water.

(10) RM 11.6, Pacific Power and Light (PP&L), Three 12KV cables under the Broadway Bridge, Depth @ 42 feet below low water.

1.4 SUMMARY. The submarine cables and pipelines were constructed under Department of the Army permits. The owners of the utilities that would be affected by the proposed channel deepening project are obligated to relocate them at their own expense in accordance with the terms of the permits for their construction.

Table 1--Columbia River Utility Crossings

No.	Location	Utility Name	Description	Impacts from CRCD
1	RM 6.5	US Coast Guard	Communications cable between Pt Adams (OR) & Chinook Pt (WA) @ 45 ft below MLLW Four - conductor telephone cable	Possible Impacts Permit #1507-24-5, 29 Nov 44 POC Seattle, WA (206) 624-2902, ext. 253
2	RM 8	US Coast Guard	Communications cable	No Impacts (no dredging conducted @ RM 8)
3	RM 9	US Dept of Commerce	Cable crossing @ 46 ft below MLLW (power to Desdomona Sands LS) Two conductors in armored submarine cable for 2400 volt circuit & three conductors for 110 volt circuit. Located @ 46 ft below MLLW	Possible Impacts CLW 124/24.1
4	RM 13.7	Pacific Telephone & Telegraph	Cable crossing between Astoria and point unknown	Unknown
5	RM 14.5	Pacific Telephone & Telegraph	Cable crossing between Astoria and Knappton (WA) Depth unknown	Unknown Permit # 1507-24-13, 22 Sep 50
6	RM 40.5	Pacific Telephone & Telegraph	Cable crossing @ 51 ft below MLLW	No Impacts
7	RM 53.5	PGE	Pipeline @ minimum 55 ft below CRD.	No Impacts

Table 1--Columbia River Utility Crossings

No.	Location	Utility Name	Description	Impacts from CRCD
8	RM 72.5 to RM 73	Unknown	Cable crossing which fronts Trojan power plant (unknown)	No Impacts (no dredging conducted between RM 72.5 and RM73)
9	RM 76.75	AT&T	Fiber optic crossing @ 62 ft below CRD	No Impacts
10	RM 76.75	NW Pipeline Corp	Pipeline crossing @ 70 ft below CRD	No Impacts
11	RM 100.4	Olympic Pipeline	Pipeline crossing @ 60 ft below CRD	No Impacts
12	RM 100.5	NW Pipeline Corp	Two 16-in natural gas pipelines. Depth of pipes @ 60 - 65 ft below LW. Project located between Sauvie Island and point near Vancouver Lake	No Impacts Permit # 1507-24-10, 28 Nov 55
13	RM 105.5	Spokane, Portland & Seattle Railroad	Communication cable crossing under railroad bridge. Depth @ 40 ft below LW.	Possible Impacts Permit # 1507-24-6, 23 Jul 45
13	RM 105.5	NW Natural Gas	Six-inch diameter pipeline located under bridge between Hayden Island and Washington shore. Depth @ 44 ft below LW.	Possible Impacts Permit # 1507-24-9, Jul 54

Table 2--Willamette River Utility Crossings

No.	Location	Utility Name	Description	Impacts from CRCDC
1	RM 2.6	NW Natural Gas Co	16-inch diameter pipeline crossing @ 80 ft below normal water surface	No Impacts
2	RM 3.5	PGE	Power cable crossing Depth unknown	Unknown
3	RM 5.8	City of Portland	36-inch diameter water line @ 60 ft below LW	No Impacts
4	RM 5.8	Pacific Telephone & Telegraph	Communications cable crossing Located under St John's Bridge Depth @ to 43 ft below LW	Possible Impacts Permit # 1507-24-29, 30 Nov 59 Permit # 1507-24-10, 21 Dec 48
5	RM 5.9	PGE	Power cable crossing Depth unknown	Unknown
6	RM 7	City of Portland	30-inch & 20-inch diameter sewer force main @ 50 ft from MLW	No Impacts
7	RM 7	Spokane, Portland & Seattle Railroad	Four armored communication cables from south side and three cables from north side. Cables @ 42 ft from MLW. Located under railroad bridge	Possible Impacts Permit # 1507-21-5, 31 Dec 70

Table 2--Willamette River Utility Crossings

No.	Location	Utility Name	Description	Impacts from CRCD
8	RM 7	NW Natural Gas Co	Gas pipeline @ 50 ft below LW	No Impacts
9	RM 7.6	Chevron Pipe	8-inch pipeline crossing @ 60 ft below LW	No Impacts Permit # 1522-15-22, 15 Jun 70
10	RM 11.25	Pacific NW Bell	Three communication cables @ 42 ft below LW	Possible Impacts Permit # 1507-24-37, 27 Aug 68
11	RM 11.25	PP&L	Cable crossing @ 37 ft below MLW	Possible Impacts Permit # 1507-24-13, 20 Aug 30
12	RM 11.25	PP&L	Six - 15 KV transmission cables & one communication cable @ 42 ft below LW	Possible Impacts Permit # 1507-24-35, 6 May 68
13	RM 11.6	PGE	Unknown. Located under Broadway Bridge	Unknown
14	RM 11.6	Pacific Telephone & Telegraph	Six communication cables. Located under Broadway Bridge @ 43 ft below LW	Possible Impacts Permit # 1507-24-16, 6 Oct 53
15	RM 11.6	PP&L	Three 12KV cables. Located under Broadway Bridge @ 42 ft below LW	Possible Impacts Permit # 1507-24-32, 12 Apr 66

CHAPTER 6 GEOTECHNICAL INFORMATION

1. Introduction.

a. Purpose. An examination of geotechnical conditions and concerns pertinent to the proposed Columbia River Channel deepening was made to assess significant features and rock quantities for adequate evaluation for the upcoming Pre-Construction Engineering and Design (PED) Phase and construction contract plans and specifications. Feasibility phase studies included review of existing data on location, size, and character of rock bodies within the proposed channel limits; on slopes and foundations for bridge piers adjacent to the channel, and coordinating efforts for mitigation of blasting effects on fish during rock removal.

b. Tasks. Geotechnical tasks completed during the Feasibility Phase Study included a search for and a review of past rock excavation information. This, and an analysis and contour update of the last 7 years of fathometer survey results, provided estimates of rock quantities to be excavated for various proposed channel alternatives. An analysis of foundation conditions for bridge piers was conducted to identify potential problems related to excavation. A preliminary cost estimate was developed for explorations and tasks to be accomplished during the PED Phase, and a plan was developed for mitigation of effects on fish during any rock removal requiring blasting.

2. Methodology.

a. Research. Geotechnical references and data pertaining to general conditions and past studies for the lower Columbia River area were reviewed for information relative to the proposed channel deepening. Data included general texts, design memorandums and previous plans and specifications for rock removal contracts. Information for bridge pier analysis was compiled from exploration information collected from State and local agencies in charge of the bridges. Blasting information was obtained from rock removal contracts from New York District, US Army Corps of Engineers for comparable navigation improvements done to Kill Van Kull and Newark Bay Channels.

b. Coordination. Port authorities and consultants, river users, and geotechnical experts were consulted regarding locations of known rock bodies and navigation hazards that could possibly be rock within or adjacent to the river channel. State and local Government and other Corps Districts provided additional information for analysis and cost projection.

c. Hydrographic Survey Analyses. Columbia and Willamette River hydrographic surveys are completed several times a year to meet the needs of river navigation and channel maintenance. These fathometer surveys accurately record simultaneously both water depths and survey instrument locations. This information is converted to elevations that represent the top of

undifferentiated soil and rock materials within the channel and adjacent areas on the survey date. Comparisons were made among all of the hydrographic surveys from 1982 to 1997 for each river reach or bar area upstream from Puget Island Bar. A compilation of the data obtained from these comparisons was used to prepare contour maps of various elevations representative of the deepest depths ever recorded within the reach during that time period. The contours were used to help locate possible rock excavation areas. Possible existing rock bodies to be excavated should only be found in these areas where previous fathometer surveys indicate that the top of undifferentiated materials has never been exposed below those elevations.

d. Rock Quantity Estimates. Rock quantities have been computed for each area where rock is known to exist or adjacent to previous excavation contracts. The Slaughters Bar, Lower Vancouver Bar, Vancouver Turning Basin, and Broadway Bridge areas are included in the rock quantities because of the difficulty of excavation, even though the materials to be excavated may not be in-place rock. Morgan Bar is included as it is suspected to contain rock, even though no explorations have been conducted to verify the existence of rock. Rock quantity estimates were prepared by computing the total amount of material that was present contained within and above the contour interval of the suspect area using the software program INROADS, version 7.0, developed by Intergraph. Basic assumptions used in preparing rock quantities are as follows:

(1) Total rock quantities present within and above a specified contour interval are identified within each known or suspect rock area as solid, in-place material.

(2) Quantities of rock material to be excavated at Slaughters Bar, Lower Vancouver Bar and Vancouver Turning Basin, all of which are on the Columbia River, are based on an elevation of -47 feet, plus one foot paid overdepth. For the Broadway Bridge reach quantities for rock material were computed to -46 plus one. For basalt to be blasted and removed in the Columbia River, quantities were computed to an elevation of -49 feet plus one. Willamette River, basalt quantities were computed to an elevation of -46 feet plus one.

(3) Only volumes inside the contour for the required excavation depth were included in the excavation rock quantities. Quantities outside the excavation contour (i.e., the areas considered to be somewhere between -49 and -50 for an overdepth of -50 feet) were not included in the paid overdepth of one foot.

(4) The swell factors used for excavation of the various materials to be encountered are 1.50 for basalt, 1.3 for Slaughters Bar, and 1.3 for the Vancouver Bar and turning basin areas, and 1.25 for the Broadway Bridge area.

(5) Top of rock was estimated from a combination of previous rock excavation contract as-designed data and from fathometer surveys as follows:

(a) Previous excavation removed all rock above at least elevation (El.) -45.5 in the Columbia River except where otherwise noted.

(b) Previous excavations removed all rock above El. -44.5 in the Willamette River except where otherwise noted.

(c) No rock occurs above the elevations indicated on hydrosurvey charts made from about 1982 through May 1997.

(6) Excavation quantities are estimated only for known or adjacent to known areas of previous rock removal except for the Slaughters Bar, Broadway Bridge, Lower Vancouver Bar and Turning Basin, and Morgan Bar areas.

(7) Excavation rock quantities include, where applicable, material present up to 10 feet outside the present channel boundaries.

(8) Quantity computations assume vertical cuts, although final rock cut slopes will be designed as 4V on 1H.

3. Geology.

a. Physiography. The lower Columbia River between Portland and its mouth crosses two distinct geologic provinces, the Puget-Willamette Lowlands and the Coast Range. The Columbia River flows north from Portland along the western border of the Puget-Willamette Lowlands and then turns westward near Longview, Washington, to traverse the Coast Range. The Willamette River flows northward within the Willamette Valley Section of the Puget-Willamette Lowlands and joins the Columbia River at Portland, Oregon. The Puget-Willamette Lowlands is a structural basin consisting mostly of alluvial plains and gently undulating hillsides with locally scattered, steeper rocky hillocks. The Coast Range trends north - south, averages about 1,500 feet in elevation, and includes numerous steep sided rapidly eroding valleys. The coastal plain is relatively narrow and at the Columbia River mouth consists mostly of an enlarged embayment. The Columbia River eroded a much deeper channel beneath the present riverbed during sea level fluctuations that occurred during the Pleistocene and Holocene (Recent) Epochs. Sea level has risen an estimated 100 feet or more during the past 15,000 years resulting in a drowned valley mouth.

b. Riverbed Materials. The ancient Columbia River Valley has been filled with widespread sand and gravel deposits from as far away as Montana and Idaho. The present riverbed consists mostly of sands and local fine silts. Rock only occurs where the river has shifted out of its previous channel over onto the previous side valley slopes. Most of this rock is expected to consist of local layers of dense, hard basalt or basalt flow breccia. Locally resistant igneous intrusives also remain at some locations. Sedimentary siltstones, sandstones, and conglomerates are less common, but also occur within the present streambed area. Materials encountered downstream from the Cowlitz River mouth in Slaughters Bar Reach and to a lesser extent in Walker Island Reach consist of cemented or compact dense gravels, cobbles, boulders, and rock blocks in a clay matrix. The Slaughters Bar materials have also been identified as rock. Whether rock or consolidated rock fragments, they can be expected to be difficult to excavate and are likely to require large excavation equipment. Fine silts from the Portland Harbor below present project maintenance depths have in the past had to be excavated during non-fish periods due to the turbidity caused by excavation.

c. Sedimentary Conditions. The lower Columbia River floodplain width varies considerably from about 1.5 to 9 miles, with numerous sand bars both natural and artificially created by deposition of dredged materials, forming islands along much of the river. Sediments tend to be deposited primarily during winter and late spring. Suspended load has been estimated to average 10^6 metric tons a year, and average bed load discharge has been estimated at the mouth as 10^5 metric tons a year. Upstream bed load must be considerably less than at the mouth since only minimum amounts of sediment have accumulated in Bonneville Lake. River bottom characteristics are continuously changing with areas of erosion and accretion occurring continuously in most areas.

4. Rock Areas and Quantities.

a. General. Locations of known and suspected rock bodies within and adjacent to the existing channel limits are discussed in the following paragraphs. Estimated rock quantities and approximate locations are presented on Table 1.

b. Wauna Bar. An area of basalt rock occurs at Wauna Bar near Columbia River Mile (CRM) 42. Rock was supposedly removed from five locations within the channel limits and from three locations adjacent to the channel in the mid-1960's. Pre-construction records indicate the rock removal pay line was to be El. -46, but the required project depth and sweep line for rock removal was to be El. -45. It can be assumed that rock was removed to at least -45.5. This reach was contoured to a bottom elevation of -50. The cumulative compilation of fathometer surveys shows no material occurring above -47. This area is shown on Figure 1.

c. Stella-Fisher Bar. A basalt rock pinnacle located near CRM 56 in the Stella-Fisher Bar Reach was excavated to approximate El. -47 in the mid-1970's. Exact depth of rock removal is not known and the specifications indicate that there was a 1- to 2-foot tolerance line for rock removal. The cumulative compilation of fathometer depths indicates the area is now greater than -47 feet. This reach was contoured to a bottom elevation of -50. This area is shown on Figure 2.

TABLE 1
COLUMBIA RIVER CHANNEL DEEPENING
ROCK EXCAVATION SUMMARY

River Reach (RR)	BORR RM*	EORR RM**	Rock Type	Required (BCY)	Required (LCY)	Paid O Depth (BCY)	Paid O Depth (LCY)	Quantity (LCY)	Area (Sq. Ft.)	Exc. Method
Columbia River	49 plus 1 and at Slaughters Bar, L. Vancouver Bar & Vancouver Turning Basin	44+27	Basalt	4,737	7,106	5,137	7,705	14,811	138,690	Drill & Blast
Wauna/Driscoll	40+40	44+27	Basalt	4,737	7,106	5,137	7,705	14,811	138,690	Drill & Blast
Stellar/Fisher Bar	55+30	59+12	Basalt	122	183	145	218	401	3,918	Drill & Blast
Slaughters Bar	63+10	67+06	Basalt	79,553	115,712	157,370	236,056	351,767	4,249,000	Clamshell
Warrior Rock	87+15	90+20	Basalt	28,387	42,581	16,641	24,961	67,542	449,300	Drill & Blast
Morgan Bar	97+40	101+18	Basalt?	38,509	57,764	36,540	54,810	112,573	986,573	Drill & Blast
L. Vancouver Bar	101+18	104+31	Gr,Bldrs,Sd	12,740	15,925	32,641	40,801	56,726	881,300	Clamshell
Van. Turn. Basin	104+31	106+23	Gr,Bldrs,Sd	47,400	59,250	89,322	111,653	170,903	2,411,700	Clamshell
Willamette River			46 plus 1, Basalt Rx. swell factor 1.5 and gravels & sand 1.25							
P.O. Range-RM 7.5	3+25	7+30	Basalt	46,219	69,329	47,845	71,833	141,096	1,291,817	Drill & Blast
RM 7.5 - Brdwy Br.	7+30	11+36	Gr,Bldrs,Sd	20,836	26,045	11,889	17,833	43,878	321,000	Clamshell
Required (BCY) - Total in-place quantity of rock above El. -49 (or 47, or 46) contour										
Required (LCY) - is the quantity of in-place material to be removed to El. -49 (or 47, or 46) swelled by 1.5 (or 1.3, or 1.25)										
Paid O Depth (BCY) - In-place Overdepth material - determined by: (areaXdepth(1 ft)) /27 f/cy= embankment yardage.										
Paid O Depth (LCY) - In-place Overdepth material swelled by 1.5 (or 1.3, or 1.25)										
Quantity (LCY) - is the total quantity of material to be removed to El. -50 (or 48, or 47), (Required (LCY) plus Paid O Depth (LCY))										
Area (Sq.Ft.) - Surface area of El. -49 (or 47, or 46) rock contour										

* BORR RM - Beginning of river reach, River Mile
 ** EORR RM - End of river reach, River Mile.
 BCY - Bank cubic yards
 LCY - Loose cubic yards

d. Slaughters Bar.

(1) General. Materials of questionable composition, but sufficiently difficult to excavate that they should be considered as rock, occur at Slaughters Bar and the upper portion of Walker Island Bar, from approximate CRM 63 to CRM 67. Materials removed from this area in the mid-1960's consisted of plastic clay and coarse gravels. Additional materials were removed in the mid-1970's, but no data could be found on the nature of these materials. Design memorandums indicate the mid-1970's material removal pay line was to be at El. -45 and the required project depth and sweep line were to be at El. -44. It can be assumed that material was removed to at least -44.5. This reach was contoured to a bottom elevation of -48. This area is shown on Figure 3.

(2) Composition of Materials. Materials to be excavated from Slaughters Bar Reach are either well cemented gravels, cobbles, boulders and displaced large rock blocks, or in-place rock. Construction data for Longview Bridge which is in the Slaughters bar Reach indicate the bridge is underlain at depth by compact sandy gravel, cobbles, and boulders, and that the piers adjacent to the channel were founded in this material at elevations of -60.7 and -72.0. A 1970 drill hole near an Oregon shore pier indicated similar materials to El -129. Bedrock beneath the river channel at the Trojan Nuclear Site (approximate river mile 73) is estimated through geophysical explorations to be below El. -300. Material thought to be in-place rock was encountered, however, in 1970 clamshell explorations at elevations as high as -40 within the channel in the vicinity of the bridge. This rock was classified at different locations as hard gray basalt, green flow breccia, or slab rock.

(3) Explanation of Interpretations. A possible explanation for the different materials encountered could be the result of past Mount St. Helens volcanic eruptions. Volcanic debris including fines, sands, gravels, cobbles, boulders, and large rock blocks could have been disgorged from the Cowlitz River mouth and deposited beneath the existing Columbia River channel, and could even have resulted in the southward relocation of the Columbia River from its original deeper channel to a much shallower channel perhaps in part flowing over rock at its present location.

(4) Difficulty of Excavation. Excavation of material from Slaughters Bar Reach is expected to be difficult, no matter which interpretation of geologic conditions or material classification is used. Clamshell explorations with a 2.5 cubic yard bucket were unable to penetrate the materials classified as rock. It is anticipated that large mechanical excavation equipment will be able to remove all material except for any in-place rock or displaced large rock blocks encountered. Blasting is not expected to be required. However, if any basalt rock or large rock blocks are encountered, blasting might be necessary.

e. Warrior Rock. An area of basalt rock occurs at Warrior Rock near CRM 87. Rock was removed from this area in the mid-1960's. Pre-construction records indicate the rock removal pay line was at El. -44, and the required project depth and sweep line for rock removal was at El. -43. It is assumed that rock has been removed to at least El. -43.5. The cumulative compilation of fathometer depths indicates rock is present above El. -45. This reach was contoured to a bottom elevation of -50. This area is shown on Figure 4.

f. Morgan Bar. A suspected rock area occurs in the Morgan Bar Reach near CRM 101. Known rock on the west bank appears to project out into the channel between approximate Stations 100+38+00 and 100+50+00. Explorations need to be accomplished in this area to verify the presence of rock. If rock is present in this area, it will probably be basalt, requiring blasting methods for removal. The cumulative compilation of fathometer depths identify material present above El. -47 feet. This reach was contoured to a bottom elevation of -50. This area is shown on Figure 5.

g. Post Office Range - River Mile 7.5. An area of basalt rock occurs in Portland Harbor within the Post Office Range - River Mile 7.5 reach between approximate Willamette River Mile (WRM) 4 and WRM 6. Rock was removed from five locations within the channel limits and from two locations adjacent to the channel. Rock excavations occurred in both the mid-1960's and again in the mid-1970's. Design memorandums for the mid-1970's excavations indicate the rock removal pay line was at El. -45 and the required project depth and sweep line for rock removal were at El. -44. Based on this, it can be assumed that rock was removed to El. -44.5. Rock could possibly be higher in some of these locations, however, since not all of the locations of the mid-1960's excavations were re-excavated in the mid-1970's. The mid-1960's rock removal pay line was at El. -43 and the rock removal line was at El. -42. Thus, some rock could possibly be found as high as approximate El. -42.5. A proposed channel realignment has been used to miss some of the known rock bodies to minimize the amount of excavation required. Rock quantities have been calculated only within the proposed channel limits. Even so, as excavation gets deeper in the vicinity of these known rock bodies, the chances of encountering additional rock increases. Results of cumulative compilation of fathometer depths has identified additional possible rock bodies or extensions of existing rock. Explorations will need to be conducted to verify the existence of rock. This reach has been contoured to a bottom elevation of -47. This area is shown on Figure 6.

h. Broadway Bridge Area. An area of known sand, gravel, and boulders is present just downstream of the Broadway Bridge, between WRM 10 and WRM 11. This area was identified through water jet probe explorations conducted during the 1960's. No information is available as to the final rock removal depth. It is anticipated that mechanical dredging equipment, such as a clamshell will be required to remove this material. Cumulative compilation of fathometer depths shows material present to around El. -43 on the northern margin of the proposed channel realignment. This portion of the reach has been contoured to a bottom elevation of -47. This area is also shown on Figure 6.

i. Lower Vancouver Bar and Turning Basin. Vancouver Bar excavations in the past have encountered considerable amounts of "...cemented sand and gravel, hard-packed sand and gravel, and cobblestones." One area encountered during the last deepening occurred near CRM 105. This area required heavy-duty mechanical dredging equipment to break up and remove the rock material. The character of this material is not consistent, cemented areas are found in a variety of areas at different elevations, making quantity estimates difficult. Cumulative compilation of fathometer depths shows material is present up to El. -46. These reaches have been contoured to a bottom elevation of -48. This area is shown on Figure 7.



5. Bridge Pier Analysis.

a. General. An analysis of the bridge piers within the channel deepening limits was made to determine the likelihood of compromising the bridge foundations by the removal of overburden or rock or through scour at the pier foundation. All available design drawings and foundation information for all bridges was secured and analyzed based on the new proposed channel depths and alignments. It was assumed that the maximum channel depth for the Columbia River was El. -48 with an El. -50 rock depth. A maximum study depth of El. -45 with an El. -46 rock depth is assumed for the Willamette River.

b. Astoria Bridge. The Astoria Bridge crosses the Columbia River at approximate River Mile 13.6. The existing channel in this location is, for the most part, deeper than the study depth, however, the channel approaches 40 feet at the southern limit. This would necessitate dredging up to 8 feet of overburden which is most likely sands and silts. There is no current information on the foundation material but design drawings indicate sand and silt to a depth of at least 80 feet. It does not appear that the maximum study depth will cause a problem with either main pier. Design drawings show the south pier to be founded slightly deeper (approximate El. -100 feet NGVD to the top of the piles) than the north pier (approximate El. -80 feet to the top of the piles) where the channel is substantially deeper than the maximum study depth. Additionally, design drawings indicate the channel was approximately -47 at the time of the contract for the bridge piers. Significant scour is not anticipated given the tidal fluctuations and the width of the river at this point.

c. Longview Bridge. The Longview Bridge crosses the Columbia River at approximate River Mile 66. There is no indication that the maximum study depth will have a detrimental effect on the bridge piers if the current channel configuration is maintained. The piers appear to be founded on gravelly sand at elevations of -60 and -72 for the main piers and -50 for the two secondary piers near each side of the shore. A current hydrosurvey of the area indicates the Longview port area limit is at least 100 feet upstream of the bridge alignment. If the port area is adjusted any nearer to the alignment of the bridge, pier #4 (closest to the north shore) will need to be examined more closely. Flows high enough to scour the gravelly sand are not anticipated in this area of the river due to the width of the channel.

d. St. Johns Bridge. The St. Johns Bridge crosses the Willamette River at approximate River Mile 5.8. It does not appear that the maximum study depth will cause a problem with either main pier. The most recent hydrosurvey indicates the channel is near or below the maximum study depth in the area of the bridge. The new Willamette channel alignment crosses beneath the bridge to the east side where the channel is the deepest. Oregon Department of Transportation drawings indicate the current channel limits are approximately 350 feet from the east main pier. Given the minimal amount of dredging in the area, the distance from the channel limit and the fact that the pier is rip-rapped to elevation -30 it is not likely the pier will be affected. The east main pier is founded on piles that have an average depth of -85 and are cut-off at -49; the foundation material is sand. The west main pier is founded into rock at least 2.0 feet at an approximate elevation of -25.

e. Burlington Northern Railroad Bridge. The Burlington Northern Railroad Bridge crosses the Willamette at approximate River Mile 6.9. Rock throughout the area is for the most part deeper than the proposed rock excavation depth of El. -46. The main west pier (no. IV), however, is founded at -45.9. A thin layer of rock extends up to about El. -43 adjacent to the pier and extends about 15 feet into the channel at El. -46. It is proposed to remove the overburden to this rock line and leave this portion of the rock intact adjacent to the pier. The main east pier is founded at a depth of approximately -80 and is not a concern. Preliminary information indicates the piers are founded on Troutdale Formation; this material is generally fairly hard cemented gravels, however, it tends to have pockets of fairly soft material.

f. Fremont Bridge. The Fremont Bridge crosses the Willamette River at approximate River Mile 11.1. The piers for this bridge are founded on land and will be unaffected by a deepening of the channel.

g. Broadway Bridge. The Broadway Bridge crosses the Willamette at approximate River Mile 11.7 and is at the upstream end of the 40-foot channel. Piers 5 and 6, in the middle of the river, are supported by timber caissons installed in the river bottom from El. -30 to -80. Materials adjacent to the caissons are anticipated to be unconsolidated sediments, based on the depth of the caissons. There is no information available on foundation material and current channel depth at the piers at this time. Underwater examinations of the piers and caissons reveal that the exposed timber framework is still intact. It is not likely a problem would be created with excavation.

6. Blasting Information.

a. General. Blasting will be required to remove in-place basalt from several areas within the Columbia and Willamette Rivers. Blasting has been accomplished in the past during previous rock removal contracts in the 1960's and 1970's. Unfortunately, very little information is available detailing how blasting was accomplished in these areas, leaving questions as to the character of the rock remaining.

b. Rock Requiring Blasting. Blasting will be required to remove rock to El. -50, which is the projected pay line, at Wauna Bar, Stella Fisher Bar, Warrior Rock, and possibly Morgan Bar on the Columbia River. Blasting will also be required to remove rock within the Willamette River at several possible locations in the Post Office Range to River Mile 7.5 Range to El. -47. Rock is all anticipated to be basalt, which is a hard, igneous rock created as a terrestrial lava flow. The character of this material is unknown, other than the hardness. Depending on location within the flow, the rock may be massive or highly jointed. Also, due to previous blasting techniques, the upper surface of areas of previous rock removal may be highly fractured, with loose material present at the surface of rock body. Explorations are required to determine the true nature of the material.

c. Proposed Blasting Plan. The proposed blasting plan is patterned after rock removal efforts conducted by New York District for channel improvements done to Kill Van Kull and

Newark Bay Channels. Rock encountered in these excavations is a diabase, which is similar to the basalt in the Columbia and Willamette Rivers. Drill holes measuring approximately 4.5 inches in diameter are to be placed on a 10-foot by 10-foot pattern drilled approximately 10 feet below the new grade line. Explosives to be used are expected to be a cartridge water gel. Rock would be removed after blasting by clamshell.

d. Mitigation of Blasting Effects on Fish. All possible measures are to be utilized to minimize blasting effects on fish during rock removal. Blasting will only be accomplished during scheduled in-water work periods. Actual blast effects will be minimized by limiting peak overpressure from blasting to 10 psi or less at the least distance possible from the shot area. This can be accomplished by ensuring every shot will have blasting delays such that explosives in each individual blast will be detonated on a different delay. This will limit the pounds of explosives per delay to about 100 pounds maximum. Information collected from other projects using this criteria indicate that peak overpressures can be controlled to 10 psi or less at distances of 30 to 50 meters from the blast point. Hazing tactics will be employed to scare fish from the immediate area just prior to each blast.

7. Explorations. Explorations are proposed for upcoming PED Phase work to better identify the location and extent of the rock bodies and to better determine the quantity and character of the material. Explorations are to begin with geophysical investigations utilizing sub-bottom profiling techniques to better determine the presence and depth of rock bodies. Once known and suspected rock bodies are better identified, a series of water jet probes and core drill holes will be placed at specific locations to verify the depth to, nature of, and quantity of rock. The nature of the rock, whether massive, jointed, slightly or highly fractured, will aid in what specific equipment or techniques will be necessary to remove the material. Planned explorations, including approximate numbers and costs are included in Attachment 1.

**COLUMBIA RIVER CHANNEL DEEPENING
SUMMARY - PED EXPLORATIONS**

GEOPHYSICAL EXPLORATIONS

Hydrosurvey Boat	\$30,000
Geophysical Contractor	\$32,400
Inspection	\$ 8,000
Contract Preparation and Administration	\$11,500
Branch S&A	\$ 2,700
Total	\$84,600

JET PROBE/CORE DRILLING EXPLORATIONS

Contract Costs	\$788,200
A/E Delivery Order Contract - Inspection	\$ 19,900
Inspection	\$ 34,400
A/E Delivery Order Contract - Contract P&S	\$ 23,800
Contract Preparation and Administration	\$ 27,100
Total	\$893,400

SLAUGHTERS BAR EXPLORATIONS

Contract Costs	\$171,000
A/E Delivery Order Contract - Inspection	\$ 19,100
Inspection	\$ 15,400
A/E Delivery Order Contract - Contract P&S	\$ 23,800
Contract Preparation and Administration	\$ 23,400
Total	\$252,700

TOTAL PED EXPLORATIONS COSTS - \$1,230,700

COLUMBIA RIVER CHANNEL DEEPENING PED - GEOPHYSICAL EXPLORATIONS

GENERAL ASSUMPTIONS

Work to be completed in 10, 10-hour days, no standby days.

Work to include a 60-mile stretch of the Columbia and 11 miles of the Willamette.

Work to be done early Summer 1999

Work to be accomplished by In-house Labor efforts

HYDROSURVEY BOAT COSTS

Boat, Crew, & PD (Hickson or Rodolf (220V)) and SEABAT - \$3,000/10-hour day

Total Boat Cost - 10 days x \$3,000/day = \$30,000

GEOPHYSICAL CONTRACTOR

Equipment - Boomer (250 Hz), GPR (50 mHz antenna), Corps Side Scan Sonar

Equipment Rate - Boomer - \$500/day, GPR - \$300/day, Side Scan - NC

Total Equipment Cost - \$800/day x 10 days + \$300 mob/demob =
\$8,300

Personnel - 2 people plus PD and Van rental

Personnel Rate - Senior Geophysicist - \$70/hr x 10 hrs = \$700/day

Staff Geophysicist - \$50/hr x 10 hrs = \$500/day

Total Personnel Cost - \$1,200/day x 10 days = \$12,000

Per Diem and Van Rental - 2 people @ \$75/day + \$50/day van = \$200/day

Total PD & Van Cost - \$200/day x 10 days = \$2,000

Data Reduction - Senior Geophysicist, 15 days @ 8 hrs/day

Total Data Reduction Cost - \$8,400

Report Preparation - Senior Geophysicist, 3 days

Total Report Cost - \$1,700

Total Cost - \$32,400

INSPECTION

Geologist, GS-11 @ \$72/hr

Inspection - \$72/hr x 10 days = \$7,200

PD - \$75/day x 8 days = \$600

Car - \$200

Total Cost - \$8,000

CONTRACT PREPARATION AND ADMINISTRATION

Geologist, GS-11 @ \$72/hr

Prepare Contract - 8 days - \$4,600

S & A - 3 days - \$1,800

Coordination - 3 days - \$1,800

Supervision, GS-13 @ \$102/hr x 8 hrs = \$800

Contracting - \$2,500

Total Contract Costs - \$11,500

BRANCH S&A (15% on In-House Labor)

Geologist, GS-11 Costs - \$17,200

Geologist, GS-13 Costs - \$800

Total Branch S&A - \$2,700

TOTAL GEOPHYSICAL EXPLORATIONS COSTS - \$84,600

COLUMBIA RIVER CHANNEL DEEPENING PED - JET PROBE/CORE DRILLING EXPLORATIONS

GENERAL ASSUMPTIONS

Work to be done in Summer 1999

Work to be done in a 60-mile stretch of the Columbia and 11-miles of the Willamette

Work to be patterned after the Coos Bay Deepening explorations in 1994 using similar equipment and production rates. Unit prices include support equipment costs.

Costs based on an average of Coos Bay bids and using a 14% inflation factor from 1994 to 1999

Explorations to last approximately 30 days

Estimate is based on using an A/E Contract vs. In-house labor efforts.

CONTRACT COSTS

Mob/Demob			\$ 88,000
Water Jet Probes			
1 st 339	Unit Price	\$1,025	\$347,000
Over 339 (115)		\$ 410	\$ 47,200
Core Drill Setups			
1 st 19	Unit Price	\$2,766	\$ 52,600
Over 19 (9)		\$1,371	\$ 12,300
Core Drilling			
1 st 190 LF	Unit Price	\$ 956	\$181,600
Over 190 LF (90)		\$ 656	\$ 59,000
		Subtotal	\$788,200

A/E DELIVERY ORDER CONTRACT - INSPECTION (Prepare Statement of Work, Coordination, S&A, etc.)

Prepare and Negotiate Statement of Work
Geologist, GS-11 - 100 hrs x \$72/hr = \$7,200

Coordination
Geologist, GS-11 - 3 days x \$72/hr = \$1,700

S&A

Geologist, GS-11 - 5 days x \$72/hr = \$2,900

Supervision, GS-13 - 4 days x \$102/hr = \$3,300

Branch S&A (15%) = \$2,300

A/E Contracting Costs (PE-TA) = \$ 2,500

Total Cost - \$ 19,900

INSPECTION (By A/E)

Geologist, GS-11 Equivalent @ \$72/hr

Inspection - \$72/hr x 10 hrs/day x 30 days = \$21,600

PD - \$75/day x 30 days = \$2,300

Car - \$500

Drill Logs, Probe Spreadsheet, and Plan Maps - \$72/hr x 7 days = \$4,000

Report - \$72/hr x 5 days = \$2,900

Profit (10%) - \$3,100

Total Cost - \$34,400

**A/E DELIVERY ORDER CONTRACT - PREPARE EXPLORATION CONTRACT
PLANS AND SPECS (Preliminary Layout of Work, Prepare and Negotiate
Statement of Work, Coordination, S&A, etc.)**

Geologist, GS-11 - 15 days x \$72/hr = \$8,600

Coordination

Geologist, GS-11 - 5 days x \$72/hr = \$2,900

S&A

Geologist, GS-11 - 5 days x \$72/hr = \$2,900

Supervision, GS-13 - 5 days x \$102/hr = \$4,100

Branch S&A (15%) = \$2,800

A/E Contracting Costs (PE-TA) = \$ 2,500

Total Cost - \$ 23,800

**EXPLORATION CONTRACT P&S PREPARATION AND ADMINISTRATION
(By A/E)**

Geologist, GS-11 Equivalent @ \$72/hr x 25 days = \$14,400

Supervision

Geologist, GS-13 Equivalent @ \$102/hr x 4 days = \$3,300

Coordination

Geologist, GS-11 Equivalent @ \$72/hr x 3 days = \$1,700

Miscellaneous Expenditures - \$2,000

Office Overhead (15%) - \$3,200

Profit (10%) - \$2,500

Total Cost - \$27,100

TOTAL JET PROBE/CORE DRILLING EXPLORATIONS COSTS - \$893,400

COLUMBIA RIVER CHANNEL DEEPENING PED - SLAUGHTERS BAR EXPLORATIONS

GENERAL ASSUMPTIONS

Assume clam shell operation digging test pits in 40 locations
Production rate of 4 test pits/day based on 1970 explorations
Assume using barge-mounted 10cy clam w/ 1 bottom dump scow, 2 tugs
Current estimate based on Coos Bay Channel Deepening Contract, 1997 using comparable equipment and rates.
Explorations to last 10 days
Estimate is based on using an A/E Contract vs. In-house labor efforts.
Work to be done Summer 1999

CONTRACT COSTS

Mob/Demob

Assume mob radius of 300 miles @ 5 mi/hr = 60 hrs

Equipment

Barge-mounted clam \$200/hr
Bottom Dump Scow \$35/hr
Tugs \$230/hr x 2
Pickups \$8/hr x 2
Total Hr Rate = \$710/hr

Mob = \$710 x 60 = \$42,600 ~ \$50,000

Demob = ½ Mob = \$25,000

Total Mob/Demob = \$75,000

Equipment and Labor Rates (Cost/Day)

Assume work 10 hr days

Equipment listed above = \$710/hr x 10 hrs = \$7,100/day x 10 days = \$71,000

Dredging Crew

Foreman - \$45/hr x 10 hrs = \$450/day

Clam Operator - \$42/hr x 10 hrs = \$420/day

Oiler - \$31/hr x 10 hrs = \$310/day

Deckhand - \$33/hr x 10 hrs = \$330/day

Total Crew Rate = \$1510/day x 10 days = \$15,000

SubTotal Cost - \$161,200 x 6% inflation for FY99

Total Contract Cost - \$171,000

A/E DELIVERY ORDER CONTRACT - INSPECTION (Prepare Statement of Work, Coordination, S&A, etc.)

Prepare and Negotiate Statement of Work
Geologist, GS-11 - 90 hrs x \$72/hr = \$6,500

Coordination
Geologist, GS-11 - 3 days x \$72/hr = \$1,700

S&A
Geologist, GS-11 - 5 days x \$72/hr = \$2,900
Supervision, GS-13 - 4 days x \$102/hr = \$3,300

Branch S&A (15%) = \$2,200
A/E Contracting Costs (PE-TA) = \$ 2,500

Total Cost - \$ 19,100

INSPECTION (By A/E)

Geologist, GS-11 Equivalent @ \$72/hr
Inspection - \$72/hr x 10 hrs/day x 10 days = \$7,200
PD - \$75/day x 10 days = \$750
Car - \$200
Exploration Logs, Spreadsheet, and Plan Maps - \$72/hr x 6 days = \$3,500
Report - \$72/hr x 4 days = \$2,300
Profit (10%) - \$1,400

Total Cost - \$15,400

A/E DELIVERY ORDER CONTRACT - PREPARE EXPLORATION CONTRACT PLANS AND SPECS (Preliminary Layout of Work, Prepare and Negotiate Statement of Work, Coordination, S&A, etc.)

Geologist, GS-11 - 15 days x \$72/hr = \$8,600

Coordination
Geologist, GS-11 - 5 days x \$72/hr = \$2,900

S&A

Geologist, GS-11 - 5 days x \$72/hr = \$2,900

Supervision, GS-13 - 5 days x \$102/hr = \$4,100

Branch S&A (15%) = \$2,800

A/E Contracting Costs (PE-TA) = \$ 2,500

Total Cost - \$ 23,800

**EXPLORATION CONTRACT P&S PREPARATION AND ADMINISTRATION
(By A/E)**

Geologist, GS-11 Equivalent @ \$72/hr x 20 days = \$11,500

Supervision

Geologist, GS-13 Equivalent @ \$102/hr x 4 days = \$3,300

Coordination

Geologist, GS-11 Equivalent @ \$72/hr x 3 days = \$1,700

Miscellaneous Expenditures - \$2,000

Office Overhead (15%) - \$2,800

Profit (10%) - \$2,100

Total Cost - \$23,400

TOTAL SLAUGHTERS BAR EXPLORATIONS COSTS - \$252,700

CHAPTER 7

BENSON BEACH DISPOSAL SITE EVALUATION

Benson Beach is located between the MCR north jetty and North Head, a rocky promontory approximately 7,500 ft north of the north jetty. The shoreline of Benson Beach has been eroding since the 1940's. The 1990-1997 shoreline recession rate averaged about 100 ft/yr. The volume of sediment loss associated with that rate is estimated to be 300,000 to 400,000 cy/yr. Several parties have suggested direct disposal of dredged material onto Benson Beach could offset erosion and reduce the need for ocean disposal. For those reasons, it was evaluated and presented in this report.

7.2 DISPOSAL OPTIONS

Disposal options at Benson Beach involve how to place dredged material on and/or offshore of the active beach. No material would be placed upland, away from the shoreline. The options range from annually placing enough sand on the beach to offset shoreline erosion, to filling the beach and offshore area back to the 1940 configuration.

It would require 300,000 to 400,000 cy/yr of disposal to counterbalance the recent erosion rate. The material could be placed along the entire beach, extending over 300 ft seaward of the high water line, or on shorter lengths with greater widths. Higher disposal rates could extend the shoreline seaward. It would require approximately 8 mcy to return the beach the 1940 shoreline, assuming a top of fill elevation of 10 ft MLLW. Sand placement would begin just above the high tide level and extend offshore about 2,000 ft. It would take two years of normal MCR maintenance dredging to get the 8 mcy needed for this fill.

7.3 DREDGING AND DISPOSAL ALTERNATIVES

Direct placement of dredged material from either the MCR or the Columbia River channels onto the beach is not feasible using current dredging practices and equipment at the projects. Beach placement would require a dredged material source, a transfer station, a connection (shorepipe) between the transfer station and beach, and heavy equipment to distribute material along the beach face. Possible methods to pump material to the beach include direct pump-out from a hopper dredge, depositing material into a sump and re-dredging with a pipeline dredge, and pumping to the beach with a system such as the Punaise submerged pump. Each of these methods are described below.

7.31 Hopper Dredge Pump-ashore. A hopper dredge pump-ashore operation would involve dredging material from the MCR channel, transporting it to a nearshore location and then using onboard pumps to pump the material to the beach. None of the hopper dredges working at the MCR or the Columbia River projects in recent years is currently

set up for direct pump ashore operations. The dredge ESSAYONS has the pump capability but would require modifications to utilize the system. It is estimated that around 0.5 mcy could be placed on Benson Beach each year using this method.

A mooring buoy would be required for the dredge to connect to a pipeline to shore. It would be necessary for the mooring location to be fairly protected from waves and currents. It may be possible to develop a location up inside Baker Bay that affords protection from larger waves and swell conditions. The area would still experience some wave activity and tidal currents. It would be necessary to dredge a deeper channel (35 foot) into the bay and a mooring location and turning basin for the dredge because Baker Bay is very shallow. The dredge ESSAYONS is 350 feet long, so the turning basin would need to be at least 500 feet across. This would involve dredging in shallow water habitat that has been identified as critical habitat for endangered salmon species and important rearing habitat for young Dungeness crabs and likely other estuarine species.

The dredging requirements to create the access channel and turning basin in Baker Bay are estimated to be 1.5 mcy and 0.5 mcy, respectively. This material is assumed to be primarily silty sand based on the surrounding environment, and would likely have to be placed at an ocean site since it is not suitable for beach nourishment. The most likely method to accomplish this dredging is with a clamshell dredge and barge. Sediment quality evaluations would need to be conducted to verify the character of the material and determine whether it is acceptable for unconfined in-water disposal. Explorations may also be required to ensure there are no rock outcroppings in the possible area, given the close proximity to the rocky headlands of Cape Disappointment.

There would be large initial costs to prepare for a pump-ashore operation. The dredge ESSAYONS would require \$400,000 to \$600,000 in modifications to be used for pump-ashore disposal. The cost of the access channel and turning basin is estimated to be between 5- and 9-million dollars and the mooring buoy cost would be in the 1 million dollar range. The total initial costs could be in the 6- to 11-million dollar range.

Typically, it takes 2 to 3 times as long to pump material out of the hopper as it does to load it, or 1 ½ to 3 hours, as opposed to bottom dumping a load in 5-20 minutes. Therefore, costs for direct pump ashore are estimated to be two to three times higher than the current practice, or about \$2.60 to \$3.90 per cubic yard. To pump sand to the far ends of the beach a booster is required, adding another \$0.70 to \$0.90 per cubic yard.

The increased time to offload the sand would cut into the available time for dredging (roughly triple the time required to dredge a given quantity), resulting in either the need for an additional dredge to complete the necessary maintenance dredging, or the project not being fully maintained. Considering the availability of dredging plant and other workloads along the West Coast, it is not realistic to expect another dredge would be available to work at the project.

7.32 Pipeline Dredge. The use of a pipeline dredge would require construction of a large sump to place MCR material in before the pipeline could pump it to Benson Beach. There

is some question that a safe and environmentally acceptable location for such a sump could be found in the vicinity of the project. Even inside of Baker Bay, the pipeline dredge used during the deepening of the Federal navigation channel in 1985 experienced difficulties with tidal currents and waves. Two possible locations for the sump were identified inside of Baker Bay and both would require considerable dredging within the bay. An onshore booster pump would also be required for pumping distances greater than about 2 miles.

One location would be near the entrance to Baker Bay, on the east side of jetty A. This would reduce the length of the access channel required for the hopper dredge and could provide a larger area for the sump. A 1 mcy capacity sump would require a basin 2,000 by 2,000 feet and 40 feet. Approximately 5 mcy would have to be dredge to create a sump this size.

Another alternative would be to locate the sump near the low area at the entrance to Fort Canby State Park. A smaller sump would be used here due to limited space. For estimation purposes, a 1,000 by 1,000 foot sump with a 500,000 cy per year capacity was evaluated. Approximately 1.5 mcy would have to be dredge to create an access channel for the hopper dredge to provide sand to the pipeline dredge. Another 2mcy would have to be dredged to create the sump.

The initial costs for the sump and turning basin for a pipeline dredge could range from 7.5 million dollars to as much as 23 million dollars, depending on the location. It would cost about 0.5 million dollars each year to mobilize the pipeline dredge and then between \$3.50 and \$4.40 per cubic yard to dredge the sump. Transporting material to the sump could cost \$0.25 to \$0.50 per cubic yard and a booster, where needed, would add another \$0.70 to \$0.90 per cubic yard.

7.33 Punaise: The Punaise has been used for beach nourishment projects in the Netherlands and it appears to have potential here. It involves use of a submerged, self-contained pump connected to shore by an umbilical cord that provides power and controls, and is run out to the pump inside of the pipeline. The system is designed to dig itself into the bottom and is therefore more protected from waves than floating plant on the surface. It is reported to be capable of pumping up to 6,000 feet without a booster in suitable conditions. The pipeline for discharge still must run up onto the beach, so it is somewhat vulnerable to waves and current. In the Netherlands, the system is used only during the summer when safe operation on the beach is possible. This system has not been used in the United States and would be considered experimental.

Because it is more protected from wave impacts, it may be possible to use this system near the north jetty or from a location offshore on peacock Spit. It would be necessary to transport additional sand to it using a hopper dredge to provide a sufficient supply for the beach. This is being done in the Netherlands. Additional evaluation and coordination with the company would be necessary to determine whether the system could be used at this location.

Preliminary cost estimates for this system are \$550,000 for mobilization, \$2.50 to 3.50 per cubic yard to pump material, and \$.70 to \$.90 per cubic yard for use of a booster. Production is estimated at 5,000 to 10,000 cubic yards per day or 0.5 to 1.0 mcy per year. These costs assume the location and material are suitable for the system and are subject to change if conditions warrant.

7.4 PLACEMENT OPTIONS

A specific plan for placement on the beach, including the quantity required and extent of coverage, has not been proposed. One method would be to place the discharge pipe as near as possible to the north jetty, and the fill would be extended to the north for up to 10,000 feet. Extending the fill to the north could be accomplished either by extending the pipeline, which may require the use of additional booster pumps, or by transporting material with earth moving equipment. In either case, the operation would require the use of heavy equipment on the beach to move the discharge pipe and redistribute sand. Typically, dredging operations would occur 24 hours a day and this type of work would be conducted during the summer months when wave conditions are lower, allowing safe operation on the beach. This operation would directly conflict with public access and recreational use of the beach and Fort Canby State Park.

7.5 CONCLUSIONS

The dredging and disposal alternatives discussed above have annual capacities of between 0.5 and 1.0 mcy per year. That is not enough capacity to handle the approximately 4 mcy dredged each year from the MCR project. The lower rate is only 0.2 mcy per year above the estimated erosion rate and it could take 40 years to refill the beach to the 1940 configuration. At the higher rate the beach could be rebuilt in about 12 years.

The Corps cannot incur the significantly greater costs and environmental impacts associated with any of these alternatives under its normal dredging authorities. There are some specific authorities for beach nourishment or beneficial uses of dredged material that would allow the Corps to pursue these alternatives. These authorities require a local sponsor to cost share in the planning and implementation of the project to place sand onto the beach, a study to determine that there is a Federal interest, and approval by Corps Headquarters. While various parties have expressed an interest in placing dredged material onto Benson beach, to date, no willing local sponsor has been identified. The Portland District would be able to spend more effort on evaluating and developing alternatives for direct placement onto the beach if a potential local sponsor is identified and is interested in evaluating any possible beneficial use alternatives.

CHAPTER 8
BASELINE COST ESTIMATE

BASELINE COST ESTIMATE
COLUMBIA RIVER CHANNEL DEEPENING
CORPS PLAN

Prepared By: CENPW-EC-DX

June 1999

SECTION 1

SUMMARY SPREAD SHEETS

****TOTAL PROJECT COST SUMMARY****

PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - BASELINE COST ESTIMATE		DISTRICT: PORTLAND		25-Jun-99										
LOCATION: COLUMBIA RIVER, OR/WA		P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION												
CURRENT MCACES ESTIMATE PREPARED:		AUTHORIZ./BUDGET YEAR: 2000		FULLY FUNDED ESTIMATE										
EFFECTIVE PRICING LEVEL:		EFFECT. PRICING LEVEL: OCT 99												
ACCOUNT NUMBER	FEATURE DESCRIPTION	COST (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (%)	TOTAL (\$K)	FEATURE MID PT	OMB (%)	COST (\$K)	CNTG (%)	TOTAL (\$K)	FULL (\$K)
09...	CHANNELS AND CANALS	114,374	16%	132,571	3.3%	118,148	16%	136,946	Oct-02	10.2%	130,199	16%	150,914	150,914
06...	ENVIRONMENTAL RESTORATION	3,505	25%	4,381	3.3%	3,621	25%	4,526	Oct-02	10.2%	3,990	25%	4,987	4,987
	TOTAL CONSTRUCTION COSTS =====>	117,879	16%	136,952	3.3%	121,769	16%	141,471		10.2%	134,189	16%	155,902	155,902
01...	LANDS AND DAMAGES (Disposal & Mitigation)	17,240	5%	18,165	3.3%	17,809	5%	18,764	Oct-00	3.3%	18,397	5%	19,384	19,384
30...	PLANNING, ENGINEERING AND DESIGN	2,400	10%	2,640	4.5%	2,508	10%	2,759	Jul-00	0.0%	2,508	10%	2,759	2,759
31...	CONSTRUCTION MANAGEMENT	7,088	10%	7,797	4.5%	7,407	10%	8,148	Oct-02	13.4%	8,399	10%	9,240	9,240
	TOTAL COST =====>	144,607	14%	165,554	3.4%	149,493	14%	171,143		9.4%	163,494	14%	187,284	187,284
	UTILITY OWNER COST FOR UTILITY RELOCATIONS	13,763	10%	15,139	3.3%	14,217	10%	15,639	Oct-02	10.2%	15,667	10%	17,234	17,234
	NON-FEDERAL DREDGE COST TO BERTHS	1,198	0%	1,198	3.3%	1,238	0%	1,238	Oct-02	10.2%	1,364	0%	1,364	1,364
	TOTAL COST =====>	159,568	3.4%	181,891	3.4%	164,948	3.4%	188,019		9.5%	180,525	3.4%	205,881	205,881

APPROVED: *Edward P. Jones* CHIEF, PLANNING AND ENGINEERING DIVISION

Davis J. March CHIEF, PROGRAMS AND PROJECT MANAGEMENT DIVISION

Peter J. Jones CHIEF, COST ENGINEERING BRANCH

APPROVAL DATE: JUL 01 1999

PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - SPONSOR PLAN COST ESTIMATE		DISTRICT: PORTLAND		25-Jun-99									
LOCATION: COLUMBIA RIVER, OR/WA		P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION											
CURRENT MCACES ESTIMATE PREPARED:		AUTHORIZ./BUDGET YEAR: 2000		FULLY FUNDED ESTIMATE									
EFFECTIVE PRICING LEVEL:		OCT-98		OCT-99									
ACCOUNT NUMBER	FEATURE DESCRIPTION	COST (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	FEATURE MID PT	CNTG (\$K)	FULL (\$K)
09...	CHANNELS AND CANALS	16,288	16%	18,901	3.3%	16,826	16%	19,525	3.3%	18,542	Oct-02	2,975	21,516
	TOTAL CONSTRUCTION COSTS =====>	16,288	16%	18,901	3.3%	16,826	16%	19,525	3.3%	18,542		2,975	21,516
01...	LANDS AND DAMAGES	0	9%	0	3.3%	0	9%	0	3.3%	0	Oct-00	0	0
30...	PLANNING, ENGINEERING AND DESIGN	335	10%	369	4.5%	350	10%	385	4.5%	350	Jul-00	35	385
31...	CONSTRUCTION MANAGEMENT	977	10%	1,075	4.5%	1,021	10%	1,123	4.5%	1,158	Oct-02	116	1,274
	TOTAL COST =====>	17,600	16%	20,344	3.4%	18,197	16%	21,033	3.4%	20,050		3,125	23,175
	UTILITY OWNER COST FOR UTILITY RELOCATIONS	10,813	10%	11,894	3.3%	11,170	10%	12,287	3.3%	12,309	Oct-02	1,231	13,540
	NON-FEDERAL DREDGE COST TO BERTHS	458	0%	458	3.3%	473	0%	473	3.3%	521	Oct-02	0	521
	TOTAL COST =====>	28,871	13.3%	32,697	3.4%	29,839	13.3%	33,793	3.4%	32,880		4,356	37,236

*****HOPPER COST SUMMARY*****

PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - BASELINE COST ESTIMATE		DISTRICT: PORTLAND		25-Jun-99										
LOCATION: COLUMBIA RIVER, OR/WA		P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION												
CURRENT MCACES ESTIMATE PREPARED:		AUTHORIZ./BUDGET YEAR: 2000		FULLY FUNDED ESTIMATE										
EFFECTIVE PRICING LEVEL:		EFFECT. PRICING LEVEL: OCT 99												
ACCOUNT	FEATURE DESCRIPTION	Oct-98 COST (\$K)	Oct-98 CNTG (%)	Oct-98 COST (\$K)	Oct-98 CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (%)	FULL (\$K)
09...	CHANNELS AND CANALS	29,687	16%	30,667	16%	35,573	3.3%	30,667	4,907	35,573	10.2%	33,795	5,407	39,202
	TOTAL CONSTRUCTION COSTS =====>	29,687	16%	30,667	16%	35,573	3.3%	30,667	4,907	35,573	10.2%	33,795	5,407	39,202
01...	LANDS AND DAMAGES	0	0%	0	0%	0	3.3%	0	0	0	3.3%	0	0	0
30...	PLANNING, ENGINEERING AND DESIGN	800	10%	836	10%	920	4.5%	836	84	920	0.0%	836	84	920
31...	CONSTRUCTION MANAGEMENT	1,781	10%	1,861	10%	2,048	4.5%	1,861	186	2,048	13.4%	2,111	211	2,322
	TOTAL COST =====>	32,268	16%	33,364	16%	38,540	3.4%	33,364	5,176	38,540	10.1%	36,741	5,702	42,443

****PIPELINE DREDGING COST SUMMARY****

PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - BASELINE COST ESTIMATE		DISTRICT: PORTLAND		25-Jun-99									
LOCATION: COLUMBIA RIVER, OR/WA		P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION											
CURRENT MCACES ESTIMATE PREPARED:		AUTHORIZ./BUDGET YEAR: 2000		FULLY FUNDED ESTIMATE									
EFFECTIVE PRICING LEVEL:		EFFECT. PRICING LEVEL: OCT 99											
ACCOUNT		COST	CNTG	TOTAL	OMB	COST	CNTG	TOTAL	FEATURE	OMB	COST	CNTG	FULL
NUMBER	FEATURE DESCRIPTION	(\$K)	(\$K)	(\$K)	(%)	(\$K)	(%)	(\$K)	MID PT	(%)	(\$K)	(\$K)	(\$K)
09...	CHANNELS AND CANALS	48,576	7,772	56,348	16%	50,179	3.3%	58,208	Oct-02	10.2%	55,297	8,848	64,145
	TOTAL CONSTRUCTION COSTS =====>	48,576	7,772	56,348	16%	50,179	3.3%	58,208		10.2%	55,297	8,848	64,145
01...	LANDS AND DAMAGES	14,455	640	15,095	4%	14,932	3.3%	15,593	Oct-00	3.3%	15,425	683	16,108
30...	PLANNING, ENGINEERING AND DESIGN	500	50	550	10%	523	4.5%	575	Jul-00	0.0%	523	52	575
31...	CONSTRUCTION MANAGEMENT	2,915	291	3,206	10%	3,046	4.5%	3,350	Oct-02	13.4%	3,454	345	3,799
	TOTAL COST =====>	66,446	8,754	75,199	13%	68,679	3.4%	77,726		8.9%	74,698	9,928	84,627

****ROCK EXCAVATION COST SUMMARY****

PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - BASELINE COST ESTIMATE		DISTRICT: PORTLAND		25-Jun-99									
LOCATION: COLUMBIA RIVER, OR/WA		P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION											
CURRENT MCACES ESTIMATE PREPARED:		AUTHORIZ./BUDGET YEAR: 2000		FULLY FUNDED ESTIMATE									
EFFECTIVE PRICING LEVEL:		EFFECT. PRICING LEVEL: OCT 99											
ACCOUNT		Oct-98		Oct-99									
NUMBER	FEATURE DESCRIPTION	COST (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (%)	TOTAL (\$K)	FEATURE MID PT	OMB (%)	COST (\$K)	CNTG (%)	FULL (\$K)
09...	CHANNELS AND CANALS	35,587	16%	41,281	3.3%	36,761	5,882	42,643	Oct-02	10.2%	40,511	6,482	46,993
	TOTAL CONSTRUCTION COSTS =====>	35,587	16%	41,281	3.3%	36,761	5,882	42,643		10.2%	40,511	6,482	46,993
01...	LANDS AND DAMAGES	0	0%	0	3.3%	0	0	0	Oct-00	3.3%	0	0	0
30...	PLANNING, ENGINEERING AND DESIGN	700	10%	770	4.5%	732	73	805	Jul-00	0.0%	732	73	805
31...	CONSTRUCTION MANAGEMENT	2,135	10%	2,349	4.5%	2,231	223	2,454	Oct-02	13.4%	2,530	253	2,783
	TOTAL COST =====>	38,422	16%	44,400	3.4%	39,724	6,178	45,902		10.2%	43,773	6,808	50,581

****MITIGATION COST SUMMARY****

PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - BASELINE COST ESTIMATE		DISTRICT: PORTLAND										25-Jun-99		
LOCATION: COLUMBIA RIVER, OR/WA		P.O.C.: PAT JONES, CHIEF, COST ENGINEERING BRANCH												
CURRENT MCACES ESTIMATE PREPARED:		Oct-98					AUTHORIZ./BUDGET YEAR: 2000							
EFFECTIVE PRICING LEVEL:		Oct-98					EFFECT. PRICING LEVEL: OCT 99							
ACCOUNT NUMBER	FEATURE DESCRIPTION	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (\$K)	TOTAL (\$K)	FEATURE MID PT	OMB (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
09...	CHANNELS AND CANALS	524	131	25%	655	3.3%	541	135	677	Oct-02	10.2%	597	149	746
	TOTAL CONSTRUCTION COSTS =====>	524	131	25%	655	3.3%	541	135	677		10.2%	597	149	746
01...	LANDS AND DAMAGES	2,785	285	10%	3,070	3.3%	2,877	294	3,171	Oct-00	3.3%	2,972	304	3,276
30...	PLANNING, ENGINEERING AND DESIGN	140	14	10%	154	4.5%	146	15	161	Jul-00	0.0%	146	15	161
31...	CONSTRUCTION MANAGEMENT	31	3	10%	35	4.5%	33	3	36	Oct-02	13.4%	37	4	41
	TOTAL COST =====>	3,480	433	12%	3,914	3.4%	3,597	448	4,045		4.4%	3,752	472	4,224

****SHILLAPOO LAKE COST SUMMARY****															
PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - BASELINE COST ESTIMATE			DISTRICT: PORTLAND						25-Jun-99						
LOCATION: COLUMBIA RIVER, OR/WA			P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION												
CURRENT MACES ESTIMATE PREPARED:			AUTHORIZ./BUDGET YEAR: 2000												
EFFECTIVE PRICING LEVEL:			EFFECT. PRICING LEVEL: OCT 99												
ACCOUNT			COST	CNTG	CNTG	TOTAL	OMB	COST	CNTG	TOTAL	FEATURE	OMB	COST	CNTG	FULL
NUMBER	FEATURE DESCRIPTION		(\$K)	(\$K)	(%)	(\$K)	(%)	(\$K)	(\$K)	(\$K)	MID PT	(%)	(\$K)	(\$K)	(\$K)
06...	ENVIRONMENTAL RESTORATION		3,465	866	25%	4,331	3.3%	3,579	895	4,474	Oct-02	10.2%	3,944	986	4,931
	TOTAL CONSTRUCTION COSTS =====>		3,465	866	25%	4,331	3.3%	3,579	895	4,474		10.2%	3,944	986	4,931
01...	LANDS AND DAMAGES		0	0	0%	0	3.3%	0	0	0	Oct-00	3.3%	0	0	0
30...	PLANNING, ENGINEERING AND DESIGN		250	25	10%	275	4.5%	261	26	287	Jul-00	0.0%	261	26	287
31...	CONSTRUCTION MANAGEMENT		208	21	10%	229	4.5%	217	22	239	Oct-02	13.4%	246	25	271
	TOTAL COST =====>		3,923	912	23%	4,835	3.4%	4,058	943	5,001		9.8%	4,452	1,037	5,489

FISHER/WALKER/LORD COST SUMMARY*															
PROJECT: COLUMBIA RIVER CHANNEL DEEPENING -BASELINE COST ESTIMATE										DISTRICT: PORTLAND		25-Jun-99			
LOCATION: COLUMBIA RIVER, OR/WA										P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION					
CURRENT MCACES ESTIMATE PREPARED:										AUTHORIZ./BUDGET YEAR: 2000		FULLY FUNDED ESTIMATE			
EFFECTIVE PRICING LEVEL:										OCT 98		OCT 99			
ACCOUNT	NUMBER	FEATURE DESCRIPTION	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (\$K)	TOTAL (\$K)	FEATURE MID PT	OMB (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
	6...	ENVIRONMENTAL RESTORATION	40	10	25%	50	3.3%	41	10	52	Oct-02	10.2%	46	11	57
		TOTAL CONSTRUCTION COSTS =====>	40	10	25%	50	3.3%	41	10	52		10.2%	46	11	57
	01...	LANDS AND DAMAGES	0	0	0%	0	3.3%	0	0	0	Oct-00	3.3%	0	0	0
	30...	PLANNING, ENGINEERING AND DESIGN	10	1	10%	11	4.5%	10	1	11	Jul-00	0.0%	10	1	11
	31...	CONSTRUCTION MANAGEMENT	2	0	10%	3	4.5%	3	0	3	Oct-02	13.4%	3	0	3
		TOTAL COST =====>	52	11	21%	64	3.6%	54	12	66		8.6%	59	13	72

SECTION 2

NARRATIVE

13 July, 1999

COLUMBIA RIVER CHANNEL DEEPENING

DRAFT BASELINE COST ESTIMATE (BCE) NARRATIVE

COLUMBIA RIVER, OR/WA

1. Project Description: The Columbia River Channel Deepening (CRCD) project would consist of deepening the existing navigation channel from RM 6.0 to RM 105.5 on the Columbia River, and RM 0.0 to RM 12.0 on the Willamette River. The channel would generally be deepened from the current authorized depth of 40 feet to a new depth of 43 feet. The typical width of the navigation channel would be 600 feet, the same as the existing channel. About 25 mcy of sand and 0.9 mcy of rock or rock-like materials would be dredged including new work and maintenance material. Hopper, pipeline and clamshell excavation methods would be employed. Hopper dredge disposal would be at designated ocean disposal sites, and flow lane sites. Disposal for pipeline and clamshell dredging would be primarily at existing and new upland disposal areas, with some flow lane disposal for rock excavated by clamshell. Three mitigation areas would be constructed. The baseline cost estimate (BCE) covers only new deepening work. No operations and maintenance dredging costs are included in the BCE.

Estimates have been prepared for two different plans, the sponsors' plan and the least cost plan. These plans differ primarily in disposal locations. The sponsors' plan proposes the use of several upland disposal areas that would be more expensive than those included in the least cost plan, because the sponsor's plan sites were a greater distance from the river reaches to be dredged. The sponsors have proposed these more distant sites because they can sustain industrial development if filled with dredge material, or the material can be sold for commercial uses. The estimate for the least cost plan is the BCE. However, the sponsors' plan may be adopted for implementation, because the sponsor has agreed to pay the difference between the cost of the sponsors plan and least cost plan.

2. Basis of Design. The basis for the design of the deepening project is given in the Feasibility Report, to be published in summer 1999.

3. Estimate References:

ER 1110-2-1302 (Civil Works Cost Engineering), APPENDIX G (Preparation of Dredge Cost Estimates)

EP 1110-1-8 (Construction Equipment Ownership and Operating Expense Schedule)

4. Construction Schedule: The proposed construction schedule is given below. Dredging is assumed to begin on June 1 each year. This schedule indicates that the proposed work can be accomplished within the 2-year construction time frame.

DREDGING REACH	VOLUME	DREDGING TYPE	PLANT
<u>YEAR 1</u>			
U/S of CRM 78	700,000	O&M	Hopper
CRM 42-78	7,800,000	Construction + O&M	2 - 30" pipelines
CRM 29-78	2,800,000	Construction + O&M	Hopper
CRM 3-29	6,500,000	Construction + O&M	2 - Hopper
CRM 63-67	240,000	Construction (Rock)	Clamshell
Columbia/Willamette	210,000	Construction (Basalt)	Drill & Blast
<u>YEAR 2</u>			
U/S of CRM 78	6,600,000	Construction + O&M	2 - 30" pipelines
D/S of CRM 78	3,000,000	O&M	30" pipeline
D/S of CRM 78	4,000,000	O&M	Hopper
Willamette River	800,000	Construction	Hopper
CRM 101-107	180,000	Construction	Clamshell
WRM 7-11	30,000	Construction	Clamshell

a. Overtime. Overtime would be necessary for the dredging and rock excavation. The hopper, pipeline and clamshell dredges would be operating 24 hours a day 7 days a week; however, there would be three shifts a day for each dredge. The drilling and shooting of rock would be 10 hours a day, 6 days a week.

b. Construction Windows. Fisheries agency concerns about fish entrapment and interference with salmon migration have resulted in designated in-water work periods in the Columbia and Willamette Rivers. The clamshell, pipeline and hopper dredging windows are year-round. The in-water work period for blasting in the Columbia River would run from November to February. In the Willamette River, the in-water work period for blasting would run from March to October (based on ODFW preferred in-water work period, prior to listing of Spring Chinook). Willamette River costs would be revised after the Portland Harbor Remediation Plan. These blasting windows would allow drilling and blasting operations to be conducted intermittently until completed.

c. Acquisition Plan. It is anticipated that construction would require two years to complete. Three major dredging contracts were planned, one for removal of common materials (primarily sand) by hopper, another for removal of common material by pipeline, and one for rock excavation. Additional dredging contracts may be required if annual funding limitations occur. Upland disposal site improvements would be accomplished during the dredging contracts.

A separate contract would be used to construct the mitigation areas. The sponsors are responsible for dredging the berths at the ports. Utility owners would be responsible for accomplishing the relocations of their underwater utilities.

5. Subcontracting Plan. No subcontracting is anticipated in any of the contracts.

6. General Estimating Information.

a. Determination of Types of Dredging. The types of dredging equipment assumed to be used, by river mile, were determined by Corps design personnel for the least cost plan, and by sponsors' personnel for the sponsors plan. Factors considered included economics (D2M2 program), river conditions, distance to disposal areas, past practice, and judgement.

b. Estimating by River Mile. The cost of the dredging was estimated river mile to adjacent river mile, in order to accurately capture costs of varying quantities, depths of cut, distances to disposal sites, and types of dredging equipment.

c. Sources of Dredging Information. Sources of dredging expertise consulted in the preparation of the BCE include: John Chew of New York District, Kim Callan of Walla Walla District, Bob Parry of Seattle District, Manson, Great Lakes, Dutra, Corps personnel from San Francisco District and Los Angeles District, and Ogden Beeman & Associates, Inc., representatives of the sponsor. There have been no large dredging contracts on the Columbia River in recent years except for hopper dredging. However, the historical dredging information used was modified to account for the conditions anticipated on the Columbia River including river flows, traffic, current and congestion in the work area.

d. Sources of Historical Data. Previous projects used as sources of historical data include: Coos Bay Channel Deepening, Oakland Harbor Channel Deepening, Los Angeles Harbor Deepening, and the Kill Van Kull Channel Deepening in New York Harbor. Historical information obtained for these projects included types of equipment used, labor crew makeups, production rates and difficulties encountered that might be similar to those anticipated for CRCDC. Additional information was obtained from modifications to these projects, which included audited monthly equipment costs. Unit costs developed in the BCE were compared to actual costs from these projects to assess reasonableness of the estimate.

e. Hazardous, Toxic and Radioactive Waste (HTRW) Remediation Costs. No specific costs for HTRW remediation were included in the BCE. A waiver was received from Higher authority, which stated that HTRW aspects did not need to be considered in the Feasibility phase, but that they must be considered in the Planning, Engineering and Design (PED) phase of the project. Costs for the HTRW explorations and analysis work, to be accomplished during PED, are included in the BCE. HTRW remediation work is expected to be minor in nature, primarily at the upland disposal sites. Therefore associated remediation costs would be relatively small. These costs are considered to be covered by contingencies in the BCE.

f. Site Access. Access to the dredging areas should not be difficult, since these areas have been dredged in the past. Access to some of the disposal areas and mitigation areas must be developed, but would generally not be difficult.

g. Rock Borrow Areas. Outfall rock at the disposal areas would be acquired from commercial quarries. Several quarries up and down the river would be used. A representative quote for the rock materials was obtained from Goble Quarry.

h. Production Rates for New Work Dredging. The new work dredging of sand materials would likely be the same rate as the usual maintenance dredging.

i. Equipment/Labor Availability. Hopper, pipeline and clamshell dredge(s) of the appropriate sizes would most likely be available on the West Coast at Seattle, San Francisco or Los Angeles. Drill boats are expected to be mobilized from the east coast (Florida) or assembled from scratch at a facility on the west coast. Appropriate crewmembers would likely come with the dredge plant.

j. Environmental Concerns. See EIS and Feasibility Report.

k. Contingencies by Feature or Sub-Feature.

1) Construction Contingency. A contingency of 16% has been used for the 09 account (hopper, pipeline and rock excavation) to cover uncertainties in all the dredging quantities, and in the unit prices for rock excavation and pipeline dredging in particular. The unit prices for hopper and clamshell dredging are more certain. The range of acceptable crew composition, operating costs, production rates, equipment availability, uncertain weather conditions, ship traffic and material variations are also covered by the construction contingency. A contingency of 25% has been used for the 09 (mitigation) to account for uncertainties in quantities and unit prices.

2) Contingencies for Functional Accounts. The contingency included in the 01 account cost is 5% for the disposal sites and 9% for the mitigation sites. Contingencies of 10% were included in the 30 and 31 accounts to cover uncertainties in engineering, design and construction management related 09 accounts discussed above.

1. Effective Dates for Labor, Equipment, Material Pricing. The effective date for all pricing is May 1998.

7. Quantities.

a. Typical Cross-Section. A cross-section sketch is provided for the typical excavation prism which shows the pre-dredge survey data, the required dredging pay depth, the maximum dredging pay depth, and the post-dredge survey data. The dredging area design width and slopes are also shown. See attachment 1.

b. Computation of Common Dredging Quantities. The quantities of common excavation were computed based on channel sounding data obtained primarily in the Winter/Spring of 1995, and on the maximum dredging pay depth. Standard dredge quantity software was used to generate the quantities. The quantities of rock excavation were deducted from the appropriate river reaches.

c. Computation of Rock Excavation Quantities. The quantities of rock excavation were computed based on historical locations of rock in the Columbia and Willamette Rivers, and the summation of condition surveys conducted over recent years. The lowest levels to which these sections of river have been dredged were considered top of rock. Then quantities of rock to be removed were computed based on the top of rock and proposed excavation depths. Rock would be excavated several feet below the proposed new authorized depth of 43 feet in order to minimize damage to dredges during future O&M dredging operations.

Quantities of the conglomerate rock to be excavated at Slaughter's Bar, Lower Vancouver Bar and Vancouver Turning Basin, all of which are on the Columbia River, were based on a depth of 47 feet, plus one foot paid overdepth. For the Broadway Bridge reach quantities for conglomerate rock were computed to 46 feet plus one. For basalt to be blasted and removed in the Columbia River, quantities were computed to a depth of 49 feet plus one. In the Willamette River, basalt quantities were computed to 46 feet plus one.

Only volumes inside the contour for the required excavation depth were included in the rock quantities. Quantities outside the excavation contour (46, 47, and 49 feet depending on location) were not included in the paid overdepth of one foot.

d. Combination of O&M and New Work Quantities. Both new work and O&M quantities would be dredged under these contracts, but only the new work costs were included in the BCE. Combining these materials would lead to greater efficiency than would be accomplished by dredging the O&M materials and then the new work materials. Dredging unit costs were estimated in CEDEP using the combined new work and O&M quantities, then the new work quantities were input into MCACES, along with the unit prices generated in CEDEP.

e. Overdepth Quantities for Dredging of Sand. Paid overdepth quantities (one foot below the required excavation line) were included in the required excavation quantity. For purposes of this estimate, all of this overdepth is assumed to be dredged, since a contractor might choose to maximize his pay amount by dredging all paid yardage. A 0.5-foot overdig amount, below the maximum dredging pay depth, was added as non-pay yardage for pipeline and clamshell estimates. For hopper dredging, non-pay yardage was determined based on historical data from sand wave dredging accomplished by the dredge Newport in recent years. See paragraph above for planned overdepth in rock.

f. Quantities Along Channel Slopes (in Sand). These slopes often slough during dredging, making it difficult to clean out the corner between the channel bottom and the slope.

This added dredging effort is accounted for by the paid overdepth, the unpaid overdepth, the added cleanup dredging time, and contingencies. For the pipeline a 5% cleanup dredging time was added and for the clamshell a 15% was added.

8. Corps of Engineers Dredge Estimating Program (CEDEP).

a. General. CEDEP was used to prepare the dredging estimates for all hopper, pipeline and clamshell dredging, including mobilization and demobilization of the dredges and associated equipment. The rock drilling and blasting, upland disposal site development, mitigation area and utility relocation estimates were prepared using MCACES. All overhead, profit and bond were computed in MCACES, not in CEDEP. The new Excel version of CEDEP was used for the hopper, pipeline and clamshell dredging estimates.

b. Dredging Areas. Areas to be dredged were provided by Cartography, by river mile. The areas to be dredged were used in CEDEP with the excavation quantities to determine the depth of cut, which has a very important effect on dredging costs.

9. Inputs to CEDEP.

a. Density of Sand. All non-rock was assumed to be loosely deposited sand weighing about 1,900 grams per liter. A material factor of 1.0 was used for this loose sand material.

b. Crew Makeups. Crew makeups were modified in CEDEP, where necessary, using recent experience on large pipeline, clamshell and hopper dredging projects.

c. Equipment Rates. CEDEP equipment rates were used in some cases, while audited equipment rates from modifications on recent dredging contracts were used in other cases.

d. Labor Rates. Labor rates were updated using recent Davis-Bacon information. A workman's compensation rate of 30% was used in CEDEP and MCACES dredging labor. This reflects longshoreman's insurance rates per review of modification estimates and discussions with SAIF personnel. Overtime percentages were computed in CEDEP and MCACES as appropriate.

e. Hydrosurveys. Hydrosurvey costs were included in CEDEP, including a survey boat and crew. Costs for pre-dredge surveys, surveys during construction and post-dredge surveys were covered.

f. Permits. No permits need to be obtained because all environmental clearances would be covered by the EIS. Thus no costs associated with permits would be incurred.

g. Fuel Price. A fuel price of \$0.70 per gallon for diesel fuel was used in the CEDEP program. This is the price for diesel fuel in the Portland area when provided in bulk to a marine

customer. An additional 1-% was added to the dredging contingency to account for significant increase in diesel fuel from September 1998 to June 1999.

h. Interest Rate, Economic Index. A cost-of-money rate of 6.25% per year was used. This was the rate in June 1998. An economic index of 6145, which reflects 2000 costs, was used.

i. Cleanup Factor. A cleanup factor of 0.95 was used for the pipeline and hopper dredging. For rock excavation a cleanup factor of 0.85 was used. This factor covers an estimated 5% and 15% additional dredging time required after the major dredging work is complete, to cleanup slopes and corners where surveys show material was missed, or where sloughing has occurred, respectively.

j. Bank Factor. The quantity for a given reach of river in combination with area to be dredged yields a bank height, which is converted to a bank factor in CEDEP. This factor varies for the different dredge types. The greater the bank factor, the more efficient the dredging operation is, up to a maximum point where no further improvement in efficiency results.

k. Effective Working Time (EWT). Dredges would typically work 7 days a week, 24 hours a day, due to the high capital expense associated with the purchase of these machines. However, maintenance activities would reduce the actual working time somewhat, based on the type of dredge, types of material being excavated, and the condition of the equipment. An EWT percentage of 80% was used for hopper and 65% for pipeline dredging based on historical performance. For basalt rock excavation the EWT was set at 50%, due to high maintenance requirements resulting for the hardness of the rock material. The nonuniform nature of the rock material also affects the EWT. The EWT for excavating the conglomerate material using a clamshell dredge is about 52%.

10. Mobilization (Mob), Demobilization (Demob) and Preparatory Work. This would vary for the different contracts, depending on how the work is broken out. CEDEP has been used to compute mob and demob for each contract.

a. Initial Mob and Demob.

1) Sand Dredging Contract. This would consist of transporting two 30" pipeline dredges, one D-8 dozer, 966 loader, 70-ton crane, ramp barge and all associated equipment, and two medium sized hopper dredge. It is anticipated that this equipment would be available from various locations on the West Coast.

2) Rock Excavation Contract. This would consist of transporting 2 drill boats, one 21 CY (13 CY in rock) clamshell dredge, two 2,000 CY scows, two 1,500 HP tugs and associated equipment.

a) Mobilization and Demobilization - Drill Boats. This has been calculated in detail for the drill boats in the backup. It is anticipated that 2 drill boats would be mobilized. Mobilization was assumed to occur from Florida. Demobilization would be back to Florida. The drill boats might be assembled from scratch at some facility on the West Coast. The cost of assembling drill boats on the West Coast would be roughly the same as mobilizing-demobilizing existing drill boats from the east coast.

A full crew, and 100% ownership and operational costs, were assumed for preparation and set-up of the drill boats. For transfer of the equipment, 25% of crew and operational costs were used, along with tug costs.

A tank barge with 60,000 lb capacity would be mobed to supply pourvex. Pourvex is the liquid explosive that would be used to blast basalt.

Initial mobilization was assumed to be to the Warrior Rock reach on the Columbia River. Interim mobilizations were assumed to the remaining rock excavation sites. Demobilization was assumed from PO Range reach on the Willamette River.

b) Mobilization and Demobilization - Off-Loading Equipment. Off-loading equipment mob/demob has also been computed in the backup. Equipment included in this activity is: 966 loader, 35-ton crane, and 16 CY rock skiff, three dump trucks and D6 cat. Equipment requirements would vary between water based off-loading and land based off-loading. Initial and interim mobs between sites were computed.

b. Interim Mobs and Demobs. These were the mobs/demobs from one reach of the river to another. There were six mob/demobs anticipated for the clamshell dredge (for rock excavation) and one for the hopper dredge. See the MCACES estimate for a listing of these mob/demobs, along with mileages from one reach to the next.

11. Hopper Dredging. Hopper dredging was estimated by the West Coast Team. Hopper dredging is assumed for use in the lower 30 miles of the Columbia River, where rough ocean conditions predominate, and at several other locations along the Columbia and Willamette Rivers where it is the more cost effective method. Disposal for hopper dredging would be accomplished at one offshore site and at eleven flowlane sites in the Columbia and Willamette Rivers. See the drawings in the main report, section 4 for locations of disposal areas. Two medium-sized hopper dredges were assumed. The Padre Island, owned by Natco, was used as the reference dredge. It has a capacity of 3,800 CY. Cycle times and production rates were computed based on recent projects on which the Padre Island was utilized. A 5% increase in dredging time was assumed for new work. Hopper dredging would be performed primarily in sand waves on the channel bottom.

12. Pipeline Dredging.

a. Determination of Pipeline Dredge Sizes. Pipeline dredge sizes were chosen as follows:

- 1) Various pipeline diameters (18", 24" and 30") were checked to obtain the least cost by river mile, but in the final analysis two 30-inch dredges were chosen in order to accomplish the work within the two-year construction contract period.
- 2) River miles were grouped together by disposal area.
- 3) Assured the dredging times were consistent with the project schedule, which calls for initial construction to be completed in 2 years.

It was decided to assume that all the new work pipeline dredging would be accomplished by two 30-inch pipeline dredges, working over two years. The first year, these two dredges would remove 7.7 mcy from downstream of RM 78. The second year, the two 30-inch dredges would remove 6.7 mcy from upstream from RM 78. In the second year, additional O&M dredging of the newly constructed channel downstream of RM 78 could add about 3 mcy of pipeline dredging and require a third 30-inch dredge.

b. Determination of Pipeline Lengths. Pipeline lengths were determined using maps generated by Cartography. Distances were scaled off from the centroid of a given RM to the centroid of the designated disposal area for that RM. Floating pipeline was assumed at a maximum of 2,500 LF, since it is the most expensive type of pipe, and this is the maximum amount of this type of pipe that is normally mobilized on a job. All other pipe used to traverse water was assumed to be submerged. Shore pipeline lengths were scaled off the maps. Average pipeline lengths were computed based on half the RM to be dredged, half the disposal area length, and the additional distance between the RM to be dredged and disposal area at their closest approach. A length of "Equivalent Additional Pipeline" was added to all pipeline estimates, in the amount of 1,000 feet. This covers any vertical height of pumping that might be required, as well as any abnormal pipeline losses.

c. Production Rates. Production rates for pipeline dredging were computed in CEDEP based on material type, bank height, pipeline lengths (distance to disposal areas), pumping horsepower, type of cutterhead, operator experience, effective working time, and cleanup time required. Standard production charts account for the above-listed data, and were used in CEDEP to compute production rates. Computed production rates are then compared to historical rates, as practicable, to assure reasonableness and are modified where appropriate.

d. Boosters. Use of boosters is sometimes necessary where pumping distances are high. The use of a booster leads to about a 15% loss in pumping efficiency per booster for the dredge, and can also be a disadvantage due to the maintenance problems they require. Occasionally their use is cost-effective; however, for long pumping distances or higher heads. CEDEP runs were performed with and without boosters to determine if booster use would yield lower unit costs.

Boosters were determined to be cost effective at several river miles on the sponsor and least cost plan.

e. Pipeline Dredge Labor Crews. A pipeline dredging crew comprised of 21 personnel, 22 when a booster was required, was used in CEDEP. This covers all personnel required to work the dredge for three 8-hour shifts per day.

f. Pipeline Dredge Shore Crew. The shore crew is composed of personnel required at the disposal site while the pipeline is dredging. This crew is comprised of: outside equipment operator foreman, two outside equipment operator, D-8L dozer with blade and winch, 966 front end loader, hydraulic crane (4wd & 45 ton), barge with ramp and three deckhands.

g. Pump Horsepower. Prime and secondary horsepower associated with the pumps on a 30-inch dredge were 9,000 and 3,310 respectively. Dredge pump horsepower relates to production rates and fuel usage.

h. Modified Dredge Areas. At a few RMs, computed bank height was too low for CEDEP to accomplish an estimate using a 30-inch dredge. At these RMs, the bank height was increased slightly to obtain output from CEDEP.

i. Variable Parameters in CEDEP. Key parameters that changed from RM to RM were: quantities, areas to be dredged, and pipeline lengths. All other parameters in the pipeline CEDEP runs remained constant from RM to RM.

13. Rock Excavation.

a. General. More details on the development of the rock excavation estimate are available in the backup material. Additional rock requiring excavation, beyond that included in the BCE, may be discovered during the PED phase of the project.

b. Mechanical Dredging. Removal of conglomerate rock in the Columbia River at RMs 63-67 and 105 would be accomplished using a clamshell dredge.

c. Blasting. Basalt in the Columbia River at RMs 87, and possibly 101, and in the Willamette River at RMs 3-7 and 10-11, would be broken up using blasting, with removal by a clamshell.

d. Dredge Type and Size. Discussions with industry personnel indicate that a 13 CY (rock) clamshell bucket would be appropriate for digging shot basalt in the Columbia River.

e. EWT for Clamshell Dredge. Based on historical record for previous rock excavation projects, an EWT of 50% was adopted for the blasted basalt to be removed at several locations. An EWT of 52% was adopted for dredging of the conglomerate materials at several other

locations. The previous projects examined included: Coos Bay Channel Deepening; John Day Drawdown: Cargill Grain Loading Facility, Rock Dredging - 1/28 to 3/6/97; and SD & Lumber Rock Dredging - 2/25 to 3/2/95; and Kill Van Kull in New York.

f. Swell Factors. The swell factors used for rock are:

- 1) Basalt: 1.50
- 2) Slaughters Bar, Vancouver Turning Basin and Lower Vancouver Turning Basin Conglomerate: 1.30
- 3) Broadway Bridge boulders, gravels & sands: 1.25

Swell of the blasted basalt was computed based on the sum of the drill plus sub-drill depths. Sub-drilling (and hence the blasting) would occur to depths deeper than the design excavation depths. Thus, swelling would occur in both the rock above the design excavation depth, but also to a depth of rock (the sub-drill depth) below the design excavation depth. This additional swelling, and requisite additional excavation, is computed in the backup and accounted for in the basalt excavation estimate.

g. Disposal of Rock Materials. Disposal of rock materials would be accomplished at the following areas:

- 1) Slaughters Bar material would go to O-64.8..
- 2) Materials from areas above and including Warrior Rock would go to Austin Point (W86.5).

Materials would be hauled on flat deck steel barges towed by 1500 hp tugs. Materials would be off-loaded at the disposal sites. A Cat 966 front end loader situated on the barge, and a 35-ton crane with a 16 CY skiff based on land were assumed for off-loading the rock. Rock would be unloaded from the skiff into dump trucks, which would haul materials to the actual disposal site. A D-6 dozer would spread the materials at the disposal site. The number of barges needed to allow for continuous excavation varies from site to site, as computed in the backup. CEDEP was used to assist in the computations. Fill factors, cycle times, production rates, and hauling times for each disposal site were computed in the backup and entered into CEDEP.

h. Blasting. Blasting would be used to loosen basalt materials. Drilling would be accomplished using drill boats similar to those owned by Great Lakes Dredge and Dock, or equivalent. These rigs were used recently on a project (Kill Van Kull) in New York that involved in-water blasting. The drill boats were about 150' by 120' in plan area, and each has 3 drills on board. A crew of about 16 people would man each drill boat. Drilling and shooting would only occur during daylight hours, because of safety concerns expressed by the Coast Guard and OSHA. Velocities in the Columbia were similar to those experienced on the New York project, so they should be tolerable. Drilling would be accomplished on a 10' x 10' pattern, using 4.5-inch diameter holes, which are 8' to 10' in depth. Steve O'Hara of Great Lakes has indicated

that the daily direct cost of one drill boat, including equipment and labor, is \$17,200/day in 1997 price level.

1) Blasting Materials and Supplies. The backup has calculations of the quantities and costs of the explosives, datacord, blasting caps, starters, and boosters anticipated to be used at the various rock excavation sites.

2) Drilling Production. Based on production levels achieved at New York Harbor, it is anticipated that 35 holes would be drilled per day by each drill boat. These holes would be drilled during one 10-hour shift per day. Drilling must be accomplished during daylight hours in the winter, therefore no more than a 10-hour shift would be used.

14. Upland Disposal Areas.

a. General. Designs for the upland disposal areas were received from the Sponsor. Designs for the disposal areas include several elements, such as dikes, spillway weirs, outfall pipes, pumping systems, utility relocations, clearing and grubbing, and access work. The containment dikes would be constructed of previously dredged sands. Ditches would be provided within the disposal areas as required to facilitate adequate drainage. Clearing and grubbing would be light.

b. Containment Dikes. Assume dike building crew would work 8 hours per day, 5 days per week. A D-8 dozer would be used for constructing dikes. The dike crew production rate is 360 LCY/hr.

c. Weirs. Weirs (spillways) have been assumed to be procured from Oregon Culvert of Tualatin, OR, (503)692-0410. Weirs would cost \$6,500 each, FOB jobsite, including a riser and 2' stub for each weir. Discharge pipe would cost \$47.00 per linear foot, FOB jobsite for 48-inch diameter 12-gage pipe. Bands, gaskets and bolts for the discharge pipe would cost \$4.50 per linear foot, FOB jobsite. About 6 hours would be required to install each weir. Rock (12-inch minus) would be placed at the end of the outfall pipes to dissipate energy from drainage water. The cost of the rock would be \$15/ton, FOB jobsite, as quoted by Goble Quarry, (503)556-9049. This is considered a typical outfall rock price for various locations along the river.

d. Return Water Pumpout Systems. Pumpout systems would be required at up to three disposal sites, and would generally be comprised of 40,000 gpm pumps at 20 feet of total head, with discharge lines. Pumping costs cover rental and operation/maintenance.

15. Mitigation Areas. Three mitigation areas are proposed. These measures are intended to improve wildlife habitat in several areas, as mitigation for construction of the upland disposal areas. Measures proposed include excavation of wetlands, dike construction, dike breaching, blockage of ditches, site tillage, irrigation, placement of snags and root wads, planting of riparian vegetation, clearing of blackberry thickets, removal of fencing, construction of water control structures, pumping, and construction of carp excluders.

16. Ecosystem Restoration. This consists of establishing wetlands in the Shillipoo Lake area, replacing 11 tide gates on the lower Columbia river at select locations, and excavating channels through spits at the upper end of Walker-Lord and Hump-Fisher Islands.

Developing the wetlands consists of constructing dikes and channels for areas or cells and installation of water control structures to regulate flow between the individuals cells. The new aluminum tide gates vary in diameter from 24 to 72 inches and have a manually operated fish slide gate attached for juvenile fish passage as needed. One or more new tide gates are to be installed at Deep River (RM 20), Grizzly Slough (RM 28), Warren Creek (RM 28), Tide Creek (RM 77), and Burris Creek (RM 81). Construction of the channels at the upper end of Walker-Lord and Hump-Fisher Islands would allow Columbia River flow into the embayments adjacent to the islands thus improving circulation and lowering water temperature.

17. Utilities Relocations. Utility owners would be responsible for relocation of utilities affected by dredging and disposal operations. The costs of utility relocations are considered in the economic analysis, but are not included in the baseline cost estimate because the utility owners must bear these costs, not the Federal Government or Sponsor.

18. Berth Dredging. Several of the container, wheat, corn and barley exporting facilities must be deepened. These costs were developed by the sponsor and are not part of the federal cost-sharing equation but are included in the total project costs for economic analysis.

19. Use of MCACES.

a. General. CEDEP results (quantities and unit prices for hopper, pipeline and clamshell dredging) were entered into MCACES in a summary manner. Portions of the BCE were directly estimated in MCACES, including rock excavation, upland disposal site construction, mitigation areas, utilities relocations, field office overhead, home office overhead, profit and bond. No land-based positioning equipment was included in the MCACES, because a ship-based global positioning system would be used for this purpose.

b. Overhead, Profit and Bond. Field office overhead (FOOH) costs include: insurance costs, project superintendent (and/or manager), project engineer, clerical staff, project trailer, sanitary, project sign, telephone, pickups, quality control, environmental protection, and other miscellaneous items. Home office overhead (HOOH) was input as a "rule of thumb" percentage for this type and size of project. A HOOH percentage of 4% was used since all contracts would likely be over \$500,000 in value. Profit was computed using the weighted guidelines sheet in MCACES. This project is not considered very risky, so the profit percentage is relatively low. Bond costs were computed using the built-in table in MCACES.

20. Functional Costs: the Task and/or Project Managers provided Functional costs associated with this work as follows:

a. 01 Account - Lands and Damages:

1) Right-of-Way Acreage: This is the land required for access to the disposal sites.

2) Disposal Site Acreage: This is the land required for the disposal sites.



b. 30 Account - Planning, Engineering and Design:

1) Plans and Specifications: This item covers preparing plans and specifications, District review, technical review, contract advertisement and award activities.


2) Engineering During Construction: This item consists of Planning and Engineering Division support to Construction Division during construction and participation in the prefinal and final inspections of the contracts.

d. 31 Account - Construction Management: This account covers construction management for the deepening contracts.

DESCRIPTIVE SKETCH PAYABLE / NON-PAYABLE DREDGE QUANTITY



PAYABLE QUANTITY EXCAVATED FROM WITHIN THE OVERALL DREDGING PAY AREA.



SLOPE AREA MATERIAL NOT DREDGED AND NOT CONSIDERED PAYABLE.



NON-PAYABLE MATERIAL EXCAVATED BEYOND THE MAXIMUM DREDGING PAY DEPTH.



NON-PAYABLE MATERIAL REMAINING WITHIN THE OVERALL DREDGING PAY AREA.

SECTION 3

MCACES PRINTOUT

Columbia River Channel Deepening
Baseline Cost Estimate
Corps of Engineers Plan

Designed By: CRCD Team
Estimated By: O'Connor/Jones

Prepared By: CENMP-DX-C

Preparation Date: 06/04/99
Effective Date of Pricing: 10/01/98

Sales Tax: 0.00%

This report is not copyrighted, but the information
contained herein is For Official Use Only.

M C A C E S for Windows
Software Copyright (c) 1985-1997
by Building Systems Design, Inc.
Release 1.2

Tri-Service Automated Cost Estimating System (TRACES)
PROJECT CRC4BC: Columbia River Channel Deepening - Baseline Cost Estimate
C. R. Channel Deepening Baseline Cost Estimate

This cost estimate is the Baseline Cost Estimate for the Integrated Feasibility Report for Channel Improvements and Environmental Impact Statement, Columbia & Lower Willamette River Federal Navigation Channel.

SUMMARY REPORTS	SUMMARY PAGE
PROJECT INDIRECT SUMMARY - Contract.....	1
PROJECT INDIRECT SUMMARY - Feature.....	2
PROJECT INDIRECT SUMMARY - Sub Feat.....	3
PROJECT INDIRECT SUMMARY - Element.....	6
PROJECT INDIRECT SUMMARY - Level 5.....	13
PROJECT INDIRECT SUMMARY - Level 6.....	25
PROJECT DIRECT SUMMARY - Contract.....	39
PROJECT DIRECT SUMMARY - Feature.....	40
PROJECT DIRECT SUMMARY - Sub Feat.....	42
PROJECT DIRECT SUMMARY - Element.....	45
PROJECT DIRECT SUMMARY - Level 5.....	52
PROJECT DIRECT SUMMARY - Level 6.....	64

DETAILED ESTIMATE	DETAIL PAGE
5. Contract #1 - Hopper	
5. Hopper Dredging	
5. Columbia River	
5. Mob-Demob.....	1
10. Dredging - Hopper	
5. Columbia River.....	1
10. Willamette River	
5. Mob-Demob.....	3
10. Dredging - Hopper	
10. Willamette River.....	3
7. Contract #2 - Pipeline	
10. Pipeline Dredging	
5. Mob-Demob	
5. Pipeline Mob-Demob.....	5
10. Shore Crew Mob-Demob.....	5
15. Pumps Mob-Demob.....	7
10. Pipeline Dredging	
10. Pipeline Dredging.....	7
20. Upland Disposal	
2. Mob and Demob.....	14
10. Upland Disposal Area Const.	
5. O-105.5 West Hayden Island	
10. Dike Construction.....	18
15. Spillway(s).....	18
20. 48" CMP Outfall Pipe.....	19
35. Utilities Relocation.....	19
25. W-97.1 Fazio Sand and Gravel	
15. Spillway(s).....	19
20. 48" CMP Outfall Pipe.....	20
30. W-96.9 Adj Fazio Sand & Gravel	
5. Clearing and Grubbing.....	20
10. Dike Construction.....	20
15. Spillway(s).....	20
20. 48" CMP Outfall Pipe.....	20
25. Spillway Extensions.....	21

DETAILED ESTIMATE

DETAIL PAGE

35. Utilities Relocation.....21
 45. Ditches.....21
 35. W-95.7
 10. Dike Construction.....21
 15. Spillway(s).....22
 20. 48" CMP Outfall Pipe.....22
 25. Spillway Extensions.....23
 45. O-90.6 Scapoose Dairy
 10. Dike Construction.....23
 15. Spillway(s).....23
 20. 48" CMP Outfall Pipe.....23
 25. Spillway Extensions.....23
 40. Access Work.....24
 47. O-87.8 Railroad Corridor
 5. Lift One
 10. Dike Construction.....24
 15. Spillway(s).....24
 20. 48" CMP Outfall Pipe.....24
 10. Lift Two
 10. Dike Construction.....24
 25. Spillway Extensions.....25
 15. Lift Three
 10. Dike Construction.....25
 25. Spillway Extensions.....25
 20. Lift Four
 10. Dike Construction.....25
 25. Spillway Extensions.....25
 50. W-86.5 Austin Point
 10. Dike Construction.....26
 15. Spillway(s).....26
 20. 48" CMP Outfall Pipe.....26
 25. Spillway Extensions.....26
 30. Outfall Rock.....26
 55. O-86.2 Sand Island
 10. Dike Construction.....27
 60. O-82.6 Reichold Chemical
 10. Dike Construction.....27
 15. Spillway(s).....27
 20. 48" CMP Outfall Pipe.....27
 25. Spillway Extensions.....27
 65. W-82.0 Martin Bar
 5. Clearing and Grubbing.....28
 10. Dike Construction.....28
 15. Spillway(s).....28
 20. 48" CMP Outfall Pipe.....28
 25. Spillway Extensions.....28
 68. W-80.0 Martin Island
 5. Clearing and Grubbing.....29
 10. Dike Construction.....29
 15. Spillway(s).....29
 20. 48" CMP Outfall Pipe.....29

DETAILED ESTIMATE	DETAIL PAGE
25. Spillway Extensions.....	29
70. 0-77.0 Lower Deer Island	
10. Dike Construction.....	30
15. Spillway(s).....	30
20. 48" CMP Outfall Pipe.....	30
25. Spillway Extensions.....	30
75. 0-75.8 Sandy Island	
10. Dike Construction.....	30
15. Spillway(s).....	31
20. 48" CMP Outfall Pipe.....	31
25. Spillway Extensions.....	31
90. W-70.1 Cottonwood Island	
5. Clearing and Grubbing.....	31
10. Dike Construction.....	31
15. Spillway(s).....	32
20. 48" CMP Outfall Pipe.....	32
25. Spillway Extensions.....	32
95. W-68.7 Howard Island	
5. Clearing and Grubbing.....	32
10. Dike Construction.....	32
15. Spillway(s).....	33
20. 48" CMP Outfall Pipe.....	33
25. Spillway Extensions.....	33
9J. 0-67.0 Rainier Beach	
10. Dike Construction.....	33
15. Spillway(s).....	33
20. 48" CMP Outfall Pipe.....	34
25. Spillway Extensions.....	34
9S. W-67.5 IP Rehandle Site	
10. Dike Construction.....	34
15. Spillway(s).....	34
20. 48" CMP Outfall Pipe.....	34
25. Spillway Extensions.....	35
A3. 0-63.5 Lord's Island - Upstream	
5. Clearing and Grubbing.....	35
10. Dike Construction.....	35
15. Spillway(s).....	35
20. 48" CMP Outfall Pipe.....	35
25. Spillway Extensions.....	36
A8. W-63.5 Reynolds's Aluminum	
15. Spillway(s).....	36
20. 48" CMP Outfall Pipe.....	36
25. Spillway Extensions.....	36
AD. W-62.0 Mt. Solo	
5. Clearing and Grubbing.....	36
10. Dike Construction.....	37
15. Spillway(s).....	37
20. 48" CMP Outfall Pipe.....	37
25. Spillway Extensions.....	37
AI. W-59.7 Hump Island	
5. Clearing and Grubbing.....	37

DETAILED ESTIMATE	DETAIL PAGE
10. Dike Construction.....	38
15. Spillway(s).....	38
20. 48" CMP Outfall Pipe.....	38
25. Spillway Extensions.....	38
AN. 0-57.0 Crims Island	
5. Clearing and Grubbing.....	38
10. Dike Construction.....	39
15. Spillway(s).....	39
20. 48" CMP Outfall Pipe.....	39
25. Spillway Extensions.....	39
AS. 0-54.0 Port Westward	
10. Dike Construction.....	39
15. Spillway(s).....	40
20. 48" CMP Outfall Pipe.....	40
25. Spillway Extensions.....	40
35. Utilities Relocation.....	40
B1. 0-42.9 James River	
10. Dike Construction.....	40
15. Spillway(s).....	41
20. 48" CMP Outfall Pipe.....	41
25. Spillway Extensions.....	41
30. Outfall Rock.....	41
B2. W-46.3 Brown Island	
5. Clearing and Grubbing.....	41
10. Dike Construction.....	42
15. Spillway(s).....	42
20. 48" CMP Outfall Pipe.....	42
25. Spillway Extensions.....	42
30. Outfall Rock.....	42
B7. W-44.0 Puget Island	
5. Clearing and Grubbing.....	43
10. Dike Construction.....	43
15. Spillway(s).....	43
20. 48" CMP Outfall Pipe.....	43
25. Spillway Extensions.....	43
35. Utilities Relocation.....	44
45. Ditches.....	44
10. Contract #3 - Rock Exc	
50. Columbia & Willamette Rivers	
5. Columbia River	
5. Rock Excavation	
5. Mob-Demob	
3. CR Slaughters Bar Reach.....	45
4. CR Warrior Rock Reach.....	45
5. CR Morgan Bar Reach.....	46
12. CR L. Van. Br. (101+18 - 104+31).....	46
10. Blasting and CEDEP Results	
3. CR Slaughter Bar 63+10 - 67+06.....	46
4. CR Warrior Rock 87+15 - 90+20.....	47
5. CR Morgan Bar 97+40 - 101+18.....	48
12. CR Van. T. B. (104+31 - 106+23).....	48

DETAILED ESTIMATE	DETAIL PAGE
17. CR L. Van. Br. (101+18 - 104+31).....	49
15. Upland Disposal - Off Load Rock	
1. Slaughter Bar Reach.....	49
2. Warrior Rock Reach.....	49
3. Morgan Bar Reach.....	49
10. Vancouver Turning Basin.....	49
15. Lower Vancouver Bar.....	49
20. Monitoring Blasting - Seismic.....	50
25. Monitoring Blasting - Press. Wav.....	50
30. Monitoring Blasting - Fish Hazin.....	50
10. Willamette River	
5. Rock Excavation	
5. Mob-demob	
6. WR PO Range Reach.....	51
7. WR Broadway Bridge Reach.....	51
10. Blasting & CEDEP Results	
6. WR PO Range 3+25 - 7+30.....	52
7. WR Broadway Bridge 7+30 - 11+36.....	53
15. Upland Disposal - Off Load. Rock	
4. WR P.O. Range Reach.....	53
5. WR Broadway Bridge Reach.....	53
20. Blasting Monitoring - Seismic.....	53
25. Blasting Monitoring - Press. Wav.....	54
30. Blasting Monitoring - Fish Hazin.....	54
20. Contract #4 - Mitigation A	
5. Mitigation Sites Mob-Demob	
5. Webb Property	
5. Mob-Demob.....	55
10. Martin Island	
5. Mob-Demob.....	55
20. Woodland Bottoms	
5. Mob-Demob.....	55
10. Mitigation Site Development	
5. Webb	
5. Site Development.....	56
10. Martin Island	
5. Site Development.....	56
20. Woodland Bottoms	
5. Site Development.....	56
25. Contract #5 - Shillapoo Lake	
5. Environmental Restoration	
5. Mob-Demob.....	57
15. Cell #1	
5. Excavation and Fill.....	57
10. Control Structure - Type A.....	58
15. Control Structure - Type B.....	59
20. Control Structure - Type C.....	59
25. Control Structure - Type A.....	60
30. Control Structure - Type B.....	60
35. Control Structure - Type C.....	61
40. Overflow Structure - Type D.....	61

DETAILED ESTIMATE	DETAIL PAGE
45. Rip Rap.....	61
20. Cell #2	
10. Control Structure - Type A.....	62
15. Control Structure - Type B.....	62
20. Control Structure - Type C.....	62
40. Overflow Structure - Type D.....	63
45. Rip Rap.....	63
25. Cell #3	
5. Excavation and Fill.....	63
10. Control Structure - Type A.....	63
15. Control Structure - Type B.....	64
20. Control Structure - Type C.....	64
40. Overflow Structure - Type D.....	65
45. Rip Rap.....	65
30. Cell #4	
5. Excavation and Fill.....	65
10. Control Structure - Type A.....	65
15. Control Structure - Type B.....	66
20. Control Structure - Type C.....	66
40. Overflow Structure - Type D.....	66
45. Rip Rap.....	67
35. Cell #5	
5. Excavation and Fill.....	67
10. Control Structure - Type A.....	67
15. Control Structure - Type B.....	67
20. Control Structure - Type C.....	68
40. Overflow Structure - Type D.....	68
45. Rip Rap.....	68
40. Cell #6	
5. Excavation and Fill.....	69
10. Control Structure - Type A.....	69
15. Control Structure - Type B.....	69
20. Control Structure - Type C.....	70
25. Clean CHN I-1 thru CHN I-3.....	70
40. Overflow Structure - Type D.....	70
45. Rip Rap.....	70
45. Cell #7	
5. Excavation and Fill.....	71
10. Control Structure - Type A.....	71
15. Control Structure - Type B.....	71
20. Control Structure - Type C.....	72
40. Overflow Structure - Type D.....	72
45. Rip Rap.....	72
50. Cell #8	
5. Excavation and Fill.....	72
10. Control Structure - Type A.....	73
15. Control Structure - Type B.....	73
20. Control Structure - Type C.....	73
25. Control Structure - Type A.....	74
30. Control Structure - Type B.....	74
35. Control Structure - Type C.....	75

DETAILED ESTIMATE	DETAIL PAGE
40. 24" HDPE.....	75
45. Excavation of Channel J.....	75
50. Overflow Structure - Type D.....	75
55. Rip Rap.....	76
55. WCS Type E.....	76
60. WCS Type F-1.....	76
63. WCS Type F-2.....	77
65. WCS Type G.....	77
70. WCS Type H.....	77
75. WCS Type I - 1.....	78
77. WCS Type I - 2.....	78
80. WCS Type J-1.....	78
82. WCS Type J-2.....	79
85. Gravel Surfacing.....	79
90. Top Soil.....	80
95. Seeding.....	80
9E. Replace 24" Tide Gate RM 77.....	80
9J. Replace 72" Tide Gate RM 28 (2).....	81
90. Replace 72" Tide Gate RM 28 (2).....	81
9T. Replace 72" Tide Gate RM 81.....	81
9Y. Replace 54" Tide Gate RM 81 (2).....	81
A3. Replace 54" Tide Gate RM 20.....	81
A8. Replace 42" Tide Gate RM 20 (2).....	82
30. Contract #6 - Fisher/Walker/Lord	
01. Mob. and Demob	
7. Mob Equipment Walker & Lord Is.....	83
12. Mob/Demob Equ. Fisher Island.....	83
10. Walker/Lord Island Channel Exca.....	84
15. Fisher Island Channel Exca.....	85
BACKUP REPORTS	BACKUP PAGE
CREW BACKUP.....	1
LABOR BACKUP.....	10
EQUIPMENT BACKUP.....	11

* * * END TABLE OF CONTENTS * * *

	QUANTITY	UOM	TOTAL DIRECT	FIELD OH	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
5	1.00	JOB	23,277,613	1,163,881	2,444,149	2,507,086	293,927	29,686,657	29686657
7	1.00	JOB	37,901,785	1,895,089	3,979,687	4,318,558	480,951	48,576,070	48576070
10	1.00	JOB	27,641,227	1,382,061	2,902,329	3,309,090	352,347	35,587,055	35587055
20	1.00	JOB	390,780	58,617	24,717	42,078	7,743	523,934	523934.31
25	1.00	JOB	2,669,995	303,594	177,230	272,749	41,078	3,464,646	3464646
30	1.00	JOB	30,938	4,022	1,748	3,124	398	40,231	40230.66
TOTAL Columbia River Channel Deepening			91,912,338	4,807,264	9,529,860	10,452,685	1,176,445	117,878,592	117878592

SPONSOR PLAN COST ESTIMATE
COLUMBIA RIVER CHANNEL DEEPENING
SPONSOR PLAN

Prepared By: CENWP-EC-DX

June 1999

SECTION 1

SUMMARY SPREAD SHEETS

****TOTAL PROJECT COST SUMMARY****

PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - SPONSOR PLAN COST ESTIMATE		DISTRICT: PORTLAND										30-Jun-99		
LOCATION: COLUMBIA RIVER, OR/WA		P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION												
CURRENT MCACES ESTIMATE PREPARED:		AUTHORIZ./BUDGET YEAR: 2000												
EFFECTIVE PRICING LEVEL:		EFFECT. PRICING LEVEL: OCT 99												
ACCOUNT	NUMBER	FEATURE DESCRIPTION	COST (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (%)	TOTAL (\$K)	FEATURE MID PT	OMB (%)	COST (\$K)	CNTG (%)	FULL (\$K)
	09...	CHANNELS AND CANALS	\$118,955	16%	138,032	3.3%	122,881	19,707	142,587	Oct-02	10.2%	135,414	21,717	157,131
	06...	ENVIRONMENTAL RESTORATION	\$3,505	25%	4,381	3.3%	3,621	905	4,526	Oct-02	10.2%	3,990	997	4,987
		TOTAL CONSTRUCTION COSTS =====>	122,460	16%	142,413	3.3%	126,501	20,611	147,113		10.2%	139,404	22,714	162,118
	01...	LANDS AND DAMAGES (Disposal & Mitigation)	17,905	5%	18,845	3.3%	18,496	971	19,467	Oct-00	3.3%	19,106	1,003	20,109
	30...	PLANNING, ENGINEERING AND DESIGN	2,400	10%	2,640	4.5%	2,508	251	2,759	Jul-00	0.0%	2,508	251	2,759
	31...	CONSTRUCTION MANAGEMENT	7,348	10%	8,084	4.5%	7,678	769	8,447	Oct-02	13.4%	8,707	872	9,579
		TOTAL COST =====>	150,113	15%	171,982	3.4%	155,183	22,602	177,786		9.4%	169,726	24,840	194,566
		UTILITY OWNER COST FOR UTILITY RELOCATIONS	13,763	10%	15,139	3.3%	14,217	1,422	15,639	Oct-02	10.2%	15,667	1,567	17,234
		NON-FEDERAL DREDGE COST TO BERTHS	1,198	0%	1,198	3.3%	1,238	0	1,238	Oct-02	10.2%	1,364	0	1,364
		TOTAL COST =====>												213,163

APPROVED: *Harold B. Jones* CHIEF, PLANNING AND ENGINEERING DIVISION

Davis J. Jones CHIEF, PROGRAMS AND PROJECT MANAGEMENT DIVISION

Patricia J. Jones CHIEF, COST ENGINEERING BRANCH

APPROVAL DATE: JUL 0 1 1999

PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - SPONSOR PLAN COST ESTIMATE		DISTRICT: PORTLAND										30-Jun-99		
LOCATION: COLUMBIA RIVER, OR/WA		P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION												
CURRENT MCACES ESTIMATE PREPARED:		OCT-98					OCT-99							
EFFECTIVE PRICING LEVEL:		OCT-98					OCT-99							
ACCOUNT NUMBER	FEATURE DESCRIPTION	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (\$K)	TOTAL (\$K)	FEATURE MID PT	OMB (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
09...	CHANNELS AND CANALS	102,667	16,464	16%	119,131	3.3%	106,055.0	17,007.3	123,062	Oct-02	10.2%	116,872.6	18,742	135,615
06...	ENVIRONMENTAL RESTORATION	3,505	876	25%	4,381	3.3%	3,620.7	905.2	4,526	Oct-02	10.2%	3,990.0	997	4,987
	TOTAL CONSTRUCTION COSTS =====>	106,172	17,340	16%	123,512	3.3%	109,675.7	17,912.5	127,588		10.2%	120,862.6	19,740	140,602
01...	LANDS AND DAMAGES	17,905	940	5%	18,845	3.3%	18,495.9	971.0	19,467	Oct-00	3.3%	19,106.2	1,003	20,109
30...	PLANNING, ENGINEERING AND DESIGN	2,065	207	10%	2,272	4.5%	2,157.9	215.8	2,374	Jul-00	0.0%	2,157.9	216	2,374
31...	CONSTRUCTION MANAGEMENT	6,385	639	10%	7,024	4.5%	6,672.3	667.2	7,340	Oct-02	13.4%	7,566.4	757	8323
	TOTAL COST =====>	132,527	19,125	14%	151,652	3.4%	137,001.8	19,766.5	156,768		9.3%	149,693.2	21,715	171,408
	UTILITY OWNER COST FOR UTILITY RELOCATIONS	2,949	295	10%	3,244	3.3%	3,046	305	3,351	Oct-02	10.2%	3,357	335.7	3,693
	NON-FEDERAL DREDGE COST TO BERTHS	740	0	0%	740	3.3%	764	0	764	Oct-02	10.2%	842	0.0	842
	TOTAL COST =====>	136,216	19,420	0%	155,636	3.4%	140,813	20,071	160,884		9.4%	153,893	22,051	175,943

****WILLAMETTE RIVER COST SUMMARY****

PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - SPONSOR PLAN COST ESTIMATE		DISTRICT: PORTLAND										30-Jun-99		
LOCATION: COLUMBIA RIVER, OR/WA		P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION												
CURRENT MCACES ESTIMATE PREPARED:		OCT-98					AUTHORIZ./BUDGET YEAR: 2000							
EFFECTIVE PRICING LEVEL:		OCT-98					EFFECT. PRICING LEVEL: OCT-99							
ACCOUNT NUMBER	FEATURE DESCRIPTION	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (\$K)	TOTAL (\$K)	FEATURE MID PT	OMB (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
09...	CHANNELS AND CANALS	16,288	2,613	16%	18,901	3.3%	16,826	2,699	19,525	Oct-02	10.2%	18,542	2,975	21,516
	TOTAL CONSTRUCTION COSTS =====>	16,288	2,613	16%	18,901	3.3%	16,826	2,699	19,525		10.2%	18,542	2,975	21,516
01...	LANDS AND DAMAGES	0	0	9%	0	3.3%	0	0	0	Oct-00	4.5%	0	0	0
30...	PLANNING, ENGINEERING AND DESIGN	335	34	10%	369	4.5%	350	35	385	Jul-00	0.0%	350	35	385
31...	CONSTRUCTION MANAGEMENT	977	98	10%	1,075	4.5%	1,021	102	1,123	Oct-02	13.4%	1,158	116	1,274
	TOTAL COST =====>	17,600	2,744	16%	20,344	3.4%	18,197	2,836	21,033		10.2%	20,050	3,125	23,175
	UTILITY OWNER COST FOR UTILITY RELOCATIONS	10,813	1,081	10%	11,894	3.3%	11,170	1,117	12,287	Oct-02	10.2%	12,309	1,231	13,540
	NON-FEDERAL DREDGE COST TO BERTHS	458	0	0%	458	3.3%	473	0	473	Oct-02	10.2%	521	0	521
	TOTAL COST =====>	28,871	3,826	0%	32,697	6.8%	29,839	3,953	34,916		0.0%	32,880	4,356	37,236

****PIPELINE DREDGING COST SUMMARY****														
PAGE 1 OF 1														
PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - SPONSOR PLAN COST ESTIMATE														
DISTRICT: PORTLAND														
LOCATION: COLUMBIA RIVER, OR/WA														
P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION														
CURRENT MCACES ESTIMATE PREPARED:														
AUTHORIZ./BUDGET YEAR: 2000														
EFFECTIVE PRICING LEVEL:														
EFFECT. PRICING LEVEL: OCT 99														
ACCOUNT NUMBER	FEATURE DESCRIPTION	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (\$K)	TOTAL (\$K)	FEATURE MID PT	OMB (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
09...	CHANNELS AND CANALS	53,318	8,531	16%	61,849	3.3%	55,077	8,812	63,890	Oct-02	10.2%	60,695	9,711	70,407
	TOTAL CONSTRUCTION COSTS =====>	53,318	8,531	16%	61,849	3.3%	55,077	8,812	63,890		10.2%	60,695	9,711	70,407
01...	LANDS AND DAMAGES	15,415	680	4%	16,095	3.3%	15,924	702	16,626	Oct-00	3.3%	16,449	726	17,175
30...	PLANNING, ENGINEERING AND DESIGN	500	50	10%	550	4.5%	523	52	575	Jul-00	0.0%	523	52	575
31...	CONSTRUCTION MANAGEMENT	3,199	320	10%	3,519	4.5%	3,343	334	3,677	Oct-02	13.4%	3,791	379	4,170
	TOTAL COST =====>	72,432	9,581	13%	82,013	3.4%	74,867	9,901	84,768		8.9%	81,458	10,868	92,326

****ROCK EXCAVATION COST SUMMARY****

PROJECT: COLUMBIA RIVER CHANNEL DEEPENING · SPONSOR PLAN COST ESTIMATE		DISTRICT: PORTLAND		30-Jun-99											
LOCATION: COLUMBIA RIVER, OR/WA		P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION													
CURRENT MCACES ESTIMATE PREPARED:		AUTHORIZ./BUDGET YEAR: 2000		FULLY FUNDED ESTIMATE											
EFFECTIVE PRICING LEVEL:		EFFECT. PRICING LEVEL: OCT 99													
ACCOUNT		OMB (%)	COST (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (%)	TOTAL (\$K)	FEATURE MID PT	OMB (%)	COST (\$K)	CNTG (%)	TOTAL (\$K)	FULL (\$K)
NUMBER	FEATURE DESCRIPTION														
09...	CHANNELS AND CANALS	3.3%	35,587	16%	41,281	3.3%	36,761	5,882	42,643	Oct-02	10.2%	40,511	6,482	46,993	
	TOTAL CONSTRUCTION COSTS =====>	3.3%	35,587	16%	41,281	3.3%	36,761	5,882	42,643		10.2%	40,511	6,482	46,993	
01...	LANDS AND DAMAGES	3.3%	0	0%	0	3.3%	0	0	0	Oct-00	3.3%	0	0	0	
30...	PLANNING, ENGINEERING AND DESIGN	4.5%	700	10%	770	4.5%	732	73	805	Jul-00	0.0%	732	73	805	
31...	CONSTRUCTION MANAGEMENT	4.5%	2,135	10%	2,349	4.5%	2,231	223	2,454	Oct-02	13.4%	2,530	253	2,783	
	TOTAL COST =====>	3.4%	38,422	16%	44,400	3.4%	39,724	6,178	45,902		10.2%	43,773	6,808	50,581	

*****MITIGATION COST SUMMARY*****														
PAGE 1 OF 1														
PROJECT:		COLUMBIA RIVER CHANNEL DEEPENING - SPONSOR PLAN COST ESTIMATE										DISTRICT: PORTLAND		30-Jun-99
LOCATION:		COLUMBIA RIVER, OR/WA										P.O.C.: PAT JONES, CHIEF, COST ENGINEERING BRANCH		
CURRENT MCACES ESTIMATE PREPARED:		Oct-98										AUTHORIZ./BUDGET YEAR: 2000		
EFFECTIVE PRICING LEVEL:		Oct-98										EFFECT. PRICING LEVEL: OCT 99		
ACCOUNT NUMBER	FEATURE DESCRIPTION	COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (\$K)	TOTAL (\$K)	FEATURE MID PT	OMB (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
09...	CHANNELS AND CANALS	483	121	25%	604	3.3%	499	125	624	Oct-02	10.2%	550	137	687
	TOTAL CONSTRUCTION COSTS =====>	483	121	25%	604	3.3%	499	125	624		10.2%	550	137	687
01...	LANDS AND DAMAGES	2,490	260	10%	2,750	3.3%	2,572	269	2,841	Oct-00	3.3%	2,657	277	2,934
30...	PLANNING, ENGINEERING AND DESIGN	140	14	10%	154	4.5%	146	15	161	Jul-00	0.0%	146	15	161
31...	CONSTRUCTION MANAGEMENT	29	3	10%	32	4.5%	30	3	33	Oct-02	13.4%	34	3	38
	TOTAL COST =====>	3,142	398	13%	3,540	3.4%	3,248	411	3,659		4.4%	3,388	433	3,820

PROJECT: COLUMBIA RIVER CHANNEL DEEPENING - SPONSOR PLAN COST ESTIMATE DISTRICT: PORTLAND 30-Jun-99
 LOCATION: COLUMBIA RIVER, OR/WA P.O.C.: PAT JONES, CHIEF, COST ENGINEERING SECTION

ACCOUNT NUMBER	FEATURE DESCRIPTION	Oct-98				Oct-99				FULLY FUNDED ESTIMATE				
		COST (\$K)	CNTG (\$K)	CNTG (%)	TOTAL (\$K)	OMB (%)	COST (\$K)	CNTG (\$K)	TOTAL (\$K)	FEATURE MID PT	OMB (%)	COST (\$K)	CNTG (\$K)	FULL (\$K)
CURRENT MCACES ESTIMATE PREPARED:														
EFFECTIVE PRICING LEVEL:														
06...	ENVIRONMENTAL RESTORATION	3,465	866	25%	4,331	3.3%	3,579	895	4,474	Oct-02	10.2%	3,944	986	4,931
	TOTAL CONSTRUCTION COSTS =====>	3,465	866	25%	4,331	3.3%	3,579	895	4,474		10.2%	3,944	986	4,931
01...	LANDS AND DAMAGES	0	0	0%	0	3.3%	0	0	0	Oct-00	3.3%	0	0	0
30...	PLANNING, ENGINEERING AND DESIGN	250	25	10%	275	4.5%	261	26	287	Jul-00	0.0%	261	26	287
31...	CONSTRUCTION MANAGEMENT	208	21	10%	229	4.5%	217	22	239	Oct-02	13.4%	246	25	271
	TOTAL COST =====>	3,923	912	23%	4,835	3.4%	4,058	943	5,001		9.8%	4,452	1,037	5,489

SECTION 2

NARRATIVE

Refer to Baseline Cost Estimate (Corp Plan).

SECTION 3

MCACES PRINTOUT

Columbia River Channel Deepening
Sponsor Plan Cost Estimate

Designed By: CRCD Team
Estimated By: O'Connor/Jones

Prepared By: CENWP-DX-C

Preparation Date: 06/02/99
Effective Date of Pricing: 10/01/98

Sales Tax: 0.00%

This report is not copyrighted, but the information
contained herein is For Official Use Only.

M C A C E S for Windows
Software Copyright (c) 1985-1997
by Building Systems Design, Inc.
Release 1.2

Tri-Service Automated Cost Accounting System (TRACES)
PROJECT CRC4SP: Columbia River Channel Deepening - Sponsor Plan Cost Estimate
CR Channel Deepening Sponsor Plan Cost Est.

This cost estimate is the recommended plan preferred by the sponsor and is for the Intergrated Feasibility Report for Channel Improvements and Environmental Impact Statement, Columbia & Lower Willamette River Federal Navigation Channel.

SUMMARY REPORTS	SUMMARY PAGE
PROJECT INDIRECT SUMMARY - Contract.....	1
PROJECT INDIRECT SUMMARY - Feature.....	2
PROJECT INDIRECT SUMMARY - Sub Feat.....	3
PROJECT INDIRECT SUMMARY - Element.....	6
PROJECT INDIRECT SUMMARY - Level 5.....	13
PROJECT INDIRECT SUMMARY - Level 6.....	25
PROJECT DIRECT SUMMARY - Contract.....	39
PROJECT DIRECT SUMMARY - Feature.....	40
PROJECT DIRECT SUMMARY - Sub Feat.....	42
PROJECT DIRECT SUMMARY - Element.....	45
PROJECT DIRECT SUMMARY - Level 5.....	52
PROJECT DIRECT SUMMARY - Level 6.....	65

DETAILED ESTIMATE	DETAIL PAGE
5. Contract #1 - Hopper	
5. Hopper Dredging	
5. Columbia River	
5. Mod-Demob.....	1
10. Dredging - Hopper	
5. Columbia River.....	1
10. Willamette River	
5. Mob-Demob.....	3
10. Dredging - Hopper	
10. Willamette River.....	3
7. Contract #2 - Pipeline	
10. Pipeline Dredging	
10. Pipeline Dredging.....	4
5. Mob -Demob	
10. Shore Crew Mob -Demob.....	11
15. Pumping Mob-Demob.....	12
5. Pipeline Mob -Demob.....	13
20. Upland Disposal Area Const	
5. Mob-Demob.....	14
10. Upland Disposal Area Const	
5. 0-105.5 West Hayden Island	
10. Dike Construction.....	18
15. Spillway(s).....	18
20. 48" CMP Outfall Pipe.....	18
35. Utilities Relocation.....	19
15. W-101.0 Gateway Parcel 3b	
5. Clearing and Grubbing.....	19
10. Dike Construction.....	19
15. Spillway(s).....	20
20. 48" CMP Outfall Pipe.....	20
25. W-97.1 Fazio Sand and Gravel	
15. Spillway(s).....	20
20. 48" CMP Outfall Pipe.....	20
40. 0-91.5 Lonestar	
5. Clearing and Grubbing.....	21

DETAILED ESTIMATE	DETAIL PAGE
15. Spillway(s).....	21
20. 48" CMP Outfall Pipe.....	21
45. Ditches.....	21
47. 0-87.8 Railroad Corridor	
5. Lift One	
10. Dike Construction.....	21
15. Spillway(s).....	22
20. 48" CMP Outfall Pipe.....	22
10. Lift Two	
10. Dike Construction.....	22
25. Spillway Extensions.....	22
15. Lift Three	
10. Dike Construction.....	22
25. Spillway Extensions.....	23
20. Lift Four	
10. Dike Construction.....	23
25. Spillway Extensions.....	23
50. W-86.5 Austin Point	
10. Dike Construction.....	23
15. Spillway(s).....	23
20. 48" CMP Outfall Pipe.....	24
25. Spillway Extensions.....	24
30. Outfall Rock.....	24
55. 0-86.2 Sand Island	
10. Dike Construction.....	24
60. 0-82.6 Reichold Chemical	
10. Dike Construction.....	24
15. Spillway(s).....	25
20. 48" CMP Outfall Pipe.....	25
25. Spillway Extensions.....	25
65. W-82.0 Martin Bar	
5. Clearing and Grubbing.....	25
10. Dike Construction.....	25
15. Spillway(s).....	26
20. 48" CMP Outfall Pipe.....	26
25. Spillway Extensions.....	26
68. W-80.0 Martin Island	
5. Clearing and Grubbing.....	26
10. Dike Construction.....	26
15. Spillway(s).....	27
20. 48" CMP Outfall Pipe.....	27
25. Spillway Extensions.....	27
70. 0-77.0 Lower Deer Island	
10. Dike Construction.....	27
15. Spillway(s).....	27
20. 48" CMP Outfall Pipe.....	28
25. Spillway Extensions.....	28
75. 0-75.8 Sandy Island	
10. Dike Construction.....	28
15. Spillway(s).....	28
20. 48" CMP Outfall Pipe.....	28

DETAILED ESTIMATE	DETAIL PAGE
25. Spillway Extensions.....	29
80. W-73.5 Peavy Rail Oval, Kalama	
15. Spillway(s).....	29
20. 48" CMP Outfall Pipe.....	29
37. RR Crossing.....	29
85. W-72.2 Kalama Northport	
15. Spillway(s).....	30
90. W-70.1 Cottonwood Island	
5. Clearing and Grubbing.....	30
10. Dike Construction.....	30
15. Spillway(s).....	30
20. 48" CMP Outfall Pipe.....	30
25. Spillway Extensions.....	31
95. W-68.7 Howard Island	
5. Clearing and Grubbing.....	31
10. Dike Construction.....	31
15. Spillway(s).....	31
20. 48" CMP Outfall Pipe.....	31
25. Spillway Extensions.....	32
9E. W-67.5 IP Rehandle Site	
10. Dike Construction.....	32
15. Spillway(s).....	32
20. 48" CMP Outfall Pipe.....	32
25. Spillway Extensions.....	32
9J. 0-67.0 Rainier Beach	
10. Dike Construction.....	33
15. Spillway(s).....	33
20. 48" CMP Outfall Pipe.....	33
25. Spillway Extensions.....	33
9Y. 0-64.8 Rainier Industrial	
5. Clearing and Grubbing.....	33
10. Dike Construction.....	34
15. Spillway(s).....	34
20. 48" CMP Outfall Pipe.....	34
25. Spillway Extensions.....	34
30. Outfall Rock.....	34
40. Access Work.....	34
A3. 0-63.5 Lord's Island - Upstream	
5. Clearing and Grubbing.....	35
10. Dike Construction.....	35
15. Spillway(s).....	35
20. 48" CMP Outfall Pipe.....	35
25. Spillway Extensions.....	35
A8. W-63.5 Reynold's Aluminum	
15. Spillway(s).....	36
20. 48" CMP Outfall Pipe.....	36
25. Spillway Extensions.....	36
AD. W-62.0 Mt. Solo	
5. Clearing and Grubbing.....	36
10. Dike Construction.....	36
15. Spillway(s).....	37

DETAILED ESTIMATE	DETAIL PAGE
20. 48" CMP Outfall Pipe.....	37
25. Spillway Extensions.....	37
A1. W-59.7 Hump Island	
5. Clearing and Grubbing.....	37
10. Dike Construction.....	37
15. Spillway(s).....	38
20. 48" CMP Outfall Pipe.....	38
25. Spillway Extensions.....	38
AN. 0-57.0 Crims Island	
5. Clearing and Grubbing.....	38
10. Dike Construction.....	38
15. Spillway(s).....	39
20. 48" CMP Outfall Pipe.....	39
25. Spillway Extensions.....	39
AS. 0-54.0 Port Westward	
10. Dike Construction.....	39
15. Spillway(s).....	39
20. 48" CMP Outfall Pipe.....	40
25. Spillway Extensions.....	40
35. Utilities Relocation.....	40
B2. W-46.3 Brown Island	
5. Clearing and Grubbing.....	40
10. Dike Construction.....	40
15. Spillway(s).....	41
20. 48" CMP Outfall Pipe.....	41
25. Spillway Extensions.....	41
30. Outfall Rock.....	41
B7. W-44.0 Puget Island	
5. Clearing and Grubbing.....	41
10. Dike Construction.....	42
15. Spillway(s).....	42
20. 48" CMP Outfall Pipe.....	42
25. Spillway Extensions.....	42
35. Utilities Relocation.....	42
45. Ditches.....	43
B9. 0-42.9 James River	
10. Dike Construction.....	43
15. Spillway(s).....	43
20. 48" CMP Outfall Pipe.....	43
25. Spillway Extensions.....	43
30. Outfall Rock.....	44
10. Contract #3 - Rock Exc	
50. Columbia & Willamette Rivers	
5. Rock Excavation	
5. Mob-Demob	
3. CR Slaughters Bar Reach.....	45
4. CR Warrior Rock Reach.....	45
5. CR Morgan Bar Reach.....	46
12. CR L. Van. Br. (101+18 -104+31).....	47
10. Blasting and CEDEP Results	

DETAILED ESTIMATE	DETAIL PAGE
3. CR Slaughter Bar 63+10 - 67+06.....	47
4. CR Warrior Rock 87+15 - 90+20.....	47
5. CR Morgan Bar 97+40 - 101+18.....	48
12. CR Van. T. B. (104+31 - 106+23).....	49
17. CR L. Van. Br. (101+18 - 104+31).....	49
15. Upland Disposal - Off Load Rock	
1. Slaughter Bar Reach.....	49
2. Warrior Rock Reach.....	50
3. Morgan Bar Reach.....	50
10. Vancouver Turning Basin.....	50
15. Lower Vancouver Bar.....	50
20. Monitoring Blasting - Seismic.....	50
25. Monitoring Blasting - Press. Wav.....	51
30. Monitoring Blasting - Fish Hazin.....	51
10. Willamette River	
5. Rock Excavation	
5. Mob-demob	
6. WR PO Range Reach.....	52
7. WR Broadway Bridge Reach.....	52
10. Blasting & CEDEP Results	
6. WR PO Range 3+25 - 7+30.....	53
7. WR Broadway Bridge 7+30 - 11+36.....	54
15. Upland Disposal - Off Load. Rock	
4. WR P.O. Range Reach.....	54
5. WR Broadway Bridge Reach.....	54
20. Blasting Monitoring - Seismic.....	54
25. Blasting Monitoring - Press. Wav.....	55
30. Blasting Monitoring - Fish Hazin.....	55
20. Contract #4 - Mitigation A	
5. Mitigation Sites Mob-Demob	
5. Webb	
5. Mob-Demob.....	56
10. Martin Island	
5. Mob-Demob.....	56
20. Woodland Bottoms	
5. Mob-Demob.....	56
10. Mitigation Site Development	
5. Webb	
5. Site Development.....	57
10. Martin Island	
5. Site Development.....	57
20. Woodland Bottoms	
5. Site Development.....	57
25. Contract #5 - Shillapoo Lake	
5. Environmental Restoration	
5. Mob-Demob.....	58
15. Cell #1	
5. Excavation and Fill.....	58
10. Control Structure - Type A.....	59
15. Control Structure - Type B.....	60
20. Control Structure - Type C.....	60

DETAILED ESTIMATE	DETAIL PAGE
25. Control Structure - Type A.....	61
30. Control Structure - Type B.....	61
35. Control Structure - Type C.....	62
40. Overflow Structure - Type D.....	62
45. Rip Rap.....	62
20. Cell #2	
10. Control Structure - Type A.....	63
15. Control Structure - Type B.....	63
20. Control Structure - Type C.....	63
40. Overflow Structure - Type D.....	64
45. Rip Rap.....	64
25. Cell #3	
5. Excavation and Fill.....	64
10. Control Structure - Type A.....	64
15. Control Structure - Type B.....	65
20. Control Structure - Type C.....	65
40. Overflow Structure - Type D.....	66
45. Rip Rap.....	66
30. Cell #4	
5. Excavation and Fill.....	66
10. Control Structure - Type A.....	66
15. Control Structure - Type B.....	67
20. Control Structure - Type C.....	67
40. Overflow Structure - Type D.....	67
45. Rip Rap.....	68
35. Cell #5	
5. Excavation and Fill.....	68
10. Control Structure - Type A.....	68
15. Control Structure - Type B.....	68
20. Control Structure - Type C.....	69
40. Overflow Structure - Type D.....	69
45. Rip Rap.....	69
40. Cell #6	
5. Excavation and Fill.....	70
10. Control Structure - Type A.....	70
15. Control Structure - Type B.....	70
20. Control Structure - Type C.....	71
25. Clean CHN I-1 thru CHN I-3.....	71
40. Overflow Structure - Type D.....	71
45. Rip Rap.....	71
45. Cell #7	
5. Excavation and Fill.....	72
10. Control Structure - Type A.....	72
15. Control Structure - Type B.....	72
20. Control Structure - Type C.....	73
40. Overflow Structure - Type D.....	73
45. Rip Rap.....	73
50. Cell #8	
5. Excavation and Fill.....	73
10. Control Structure - Type A.....	74
15. Control Structure - Type B.....	74

DETAILED ESTIMATE	DETAIL PAGE
20. Control Structure - Type C.....	74
25. Control Structure - Type A.....	75
30. Control Structure - Type B.....	75
35. Control Structure - Type C.....	76
40. 24" HDPE.....	76
45. Excavation of Channel J.....	76
50. Overflow Structure - Type D.....	76
55. Rip Rap.....	77
55. MCS Type E.....	77
60. MCS Type F-1.....	77
63. MCS Type F-2.....	78
65. MCS Type G.....	78
70. MCS Type H.....	78
75. MCS Type I - 1.....	79
77. MCS Type I - 2.....	79
80. MCS Type J-1.....	79
82. MCS Type J-2.....	80
85. Gravel Surfacing.....	80
90. Top Soil.....	81
95. Seeding.....	81
9E. Replace 24" Tide Gate RM 77.....	81
9J. Replace 72" Tide Gate RM 28 (2).....	82
90. Replace 72" Tide Gate RM 28 (2).....	82
9T. Replace 72" Tide Gate RM 81.....	82
9Y. Replace 54" Tide Gate RM 81 (2).....	82
A3. Replace 54" Tide Gate RM 20.....	82
A8. Replace 42" Tide Gate RM 20 (2).....	83
30. Contract #6 - Fisher/Walker/Lord	
01. Mob. and Demob	
7. Mob Equipment Walker & Lord Is.....	84
12. Mob/Demob Equ. Fisher Island.....	84
10. Walker/Lord Island Channel Exca.....	85
15. Fisher Island Channel Exca.....	86
BACKUP REPORTS	BACKUP PAGE
CREW BACKUP.....	1
CREW BACKUP - Level 6.....	10
LABOR BACKUP.....	12
LABOR BACKUP - Level 6.....	13
EQUIPMENT BACKUP.....	16
EQUIPMENT BACKUP - Level 6.....	17

* * * END TABLE OF CONTENTS * * *

	QUANTITY	UOM	TOTAL DIRECT	FIELD OH	HOME OFC	PROFIT	BOND	TOTAL COST	UNIT COST
5	1.00	JOB	23,183,777	1,159,189	2,434,297	2,496,980	292,742	29,566,985	29566984.58
7	1.00	JOB	41,601,704	2,080,085	4,368,179	4,740,129	527,901	53,317,999	53317998.54
10	1.00	JOB	27,641,227	1,382,061	2,902,329	3,309,090	352,347	35,587,055	35587054.75
20	1.00	JOB	359,891	53,984	22,763	38,752	7,131	482,520	482520.20
25	1.00	JOB	2,669,995	303,594	177,230	272,749	41,078	3,466,646	3466645.85
30	1.00	JOB	30,938	4,022	1,748	3,124	398	40,231	40230.66

TOTAL	1.00	EA	95,487,533	4,982,935	9,906,545	10860824	1,221,598	122,459,435	122459434.58

