

### Elk Creek Dam Fish Passage Corridor





### **Project Location**

**Portland District** 





### **Project History**

- Project authorization
  - Part of 1962 Flood Control Act (three projects)
  - Lost Creek completed in 1976
  - Applegate completed in 1980
- Elk Creek construction
  - Initiated in 1971 (multi-purpose & flood control)
  - Deferred in 1977 due to lack of state support
  - Restarted in 1985 after review by Corps Water Policy Review Board
- Project stopped by injunction in 1988 at 1/3 of design height



### **Project History**

- 1988-1995 Corps works to restart construction
  - Petitioned court to remove injunction to allow Congress to decide whether to complete the project
  - Prepared additional environmental documentation, including a "no pool alternative" (2<sup>nd</sup> EIS supplement)
- 1995 Appeals Court decision
  - Left injunction against project completion in place
  - Required comprehensive review of a wide range of issues in additional environmental documentation
- 1995 Corps notifies Congress
  - Will not perform studies required to remove injunction
  - Will implement long-term management plan to preserve majority of federal investment




### Fish Passage Issue

- Initial project plan included eliminating Elk Creek's wild fish run
- Called for hatchery production to replace the wild run
- 1988–1991
  - Juvenile salmon pass downstream through diversion tunnel
  - No adult salmon migrating upstream
- 1992 temporary fish trap constructed to collect fish for hatchery brood stock



### Fish Passage Issue


- Coho salmon were listed as threatened under Endangered Species Act in May 1997, raising level of concern and obligation for fish passage
- 1997 Congressional Appropriations Act requires Corps to provide "passive" fish passage
- Temporary Trap
  - Built to last five years
  - Increasing weir and pump failures





╢

### Weir Failure





# Studies of Fish Passage Alternatives with an Incomplete Dam

- 1998 EA for passive passage (notch) analyzed 4 alternatives
  - Public comment considered
  - Corps issued FONSI (Finding of No Significant Impact)
  - Project stopped due to funds constraints
- 2000 Major Alternative Study (Design Memo No. 10, Supplement No. 4)
  - Six alternatives screened to four
  - Included analysis of four alternatives and new trap & haul
  - Notch recommended



### Cost Comparison

(Design Memorandum No. 10, Supplement No. 4)

- New Trap & Haul
  - Construction @ \$ 8.4 M
  - 50 yr annual @ \$ 1 M
  - 10 yr annual @ \$ 1.67 M

- Passage Corridor
  - Construction @ \$7.1 M
  - ◆ 50 yr annual @ \$ 596 K
  - 10 yr annual @ \$ 1.1 M

NOTE: Above data is at 1998 Price Levels and interest rates. Fish passage corridor costs less to build, about 60% of trap and haul over 50 years, and slightly less than trap and haul at 10 years



### **Biological Comparison**

(Design Memorandum No. 10, Supplement No. 4)

- Permanent (new) trap & haul facility
  - 1997 ESA states preference for "passive" passage
  - Increases:
    - stress/injury/mortality from handling fish
    - potential for trap rejection (fish don't go in)
    - juvenile passage through debris
    - **risk of system failure**
- Fish passage corridor & stream restoration
  - Lowest risk and eliminates trap & haul issues



### Studies of Fish Passage Alternatives with an Incomplete Dam

- 2001 draft Supplemental EA for Notch analyzed 4 alternatives
  - Notch & stream restoration
  - Temporary trap & haul
  - New trap & haul
  - Diversion tunnel
- 2001 Endangered Special Act consultation (BA/BIOP) short listed to two alternatives
  - Notch
  - New trap and haul
- Work stopped due to funds constraints



# 2007 Environmental Assessment

(picking up where we left off in 2001)

- FY 2007 funds appropriated to resume studies
- Public comment with focus on the two alternatives
  - Passage corridor & stream restoration (Proposed Action in 2008)
  - Replacement of trap & haul (the No Action alternative)
  - Written comments by November 5, 2007 to:

**District Engineer** 

**US Army Corps of Engineers, Portland** 

**Attn: CENWP-PM-E** 

PO Box 2946

Portland, OR 97208-2946



### Proposed Action Fish Passage Corridor

- Remove part of dam and spillway
  - ◆ 50,000 cy of RCC
  - 15,000 cy of conventional concrete
- Re-align 5,000 ft of Elk Creek channel to original
  - 275,000 cy of cut and fill
  - 1,000 cy or rock excavation
- Build 14,000 cy training wall
- Restore streambed (plantings, boulders, ect.)
- Implementation in Fiscal Year 2008



# 2008 Authorization & Appropriations

- Congressional report language which prohibited notch was deemed advisory and not statutory
- FY 2008 \$10M appropriated for project construction
- Construction procurement initiated
  - Up-date Design Document
  - Up-date Request for Proposal
  - Complete Value Engineering (October 2007)
  - Advertise contract (December 2007)
  - Bids were received (January 2008)



### Design/Build Contract

- Contract awarded in February 2008 to:
   McMillen McDougall
   20182 SW 112th Ave
   Tualatin, OR 97062
- On-site construction started May, 2008
- Design was completed June, 2008



### Design Objectives


- Provide and maintain fish passage from 1 cfs to 5,000 cfs
- Replicate natural conditions
- Restore or replace existing dikes (rock weirs)
- Provide resting areas for fish
- Remove solid and/or hazardous waste




### Major Features

- Re-grade stream below Dam
- Notch through the RCC dam
- Re-grade stream up-stream of dam
- Care and diversion of water
- Stream channel design
- Bank stabilization

#### Elk Creek Dam Fish Passage Corridor - upstream



### Elk Creek Dam Fish Passage Corridor – Dam Plan & Section






### Construction Sequence

- Haul roads, bridges, access
- Care and diversion of water
- Fish salvage operations
- Channel excavation
- Dam notch excavation
- Construct channel features
  - Gravel blanket, boulders, rock weirs, woody debris
  - Rip rap, geotextile blanket, plantings
- Diversion thru new channel





## Upstream Before & After






### Downstream Before & After





US Army Corps of Engineers

### **Aerial View**





### Summary

- Partially complete Elk Creek Dam
- ESA listing of Coho & fish passage issue
- Multiple studies and ESA consultation
- Fish Passage Corridor
  - most biologically sound
  - least cost solution w/ incomplete dam
  - preserves majority of federal investment in dam
- Phase I substantially complete in FY 2008
- Phase II continued restoration in FY 2009